

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
					ROADWAY	SURVEILLANCE	BRIDGE SN 022-0101 SN 022-0102	BRIDGE (See Note A)
					90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
			URBAN					
					1000-2A	Y092-1F	X271-2A	X271-2A
	20101400	NITROGEN FERTILIZER NUTRIENT	POUND	41	41			
**	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18			
	20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	41	41			
**	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18			
	20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	41	41			
**	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18			
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	313				313
	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	132				132
	21101606	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	371	371			
	25000350	SEEDING, CLASS 7	ACRE	0.5	0.5			
	25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5			
	25100115	MULCH, METHOD 2	ACRE	1	1			
**	25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.7	0.7			
**	25100630	EROSION CONTROL BLANKET	SQ YD	4540	4540			
**	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1440	1440			
**	28000400	PERIMETER EROSION BARRIER	FOOT	1,100	1,100			
**	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	480	480			
	28000510	INLET FILTERS	EACH	25	25			
**	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	48	48			
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	545	545			
	40600300	AGGREGATE (PRIME COAT)	TON	2,723	2,723			
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1,021	1,021			
**	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	4540	4540			
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
**	44003800	MEDIAN SURFACE REMOVAL	SQ FT	40,850	40,850			
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	5,200	5,200			
**	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	48	48			
	40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1,500	1,500			
	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	7,453	7,453			
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	29,597	29,597			
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	19,729	19,729			
	42001200	PAVEMENT FABRIC	SQ YD	226	226			
	42001300	PROTECTIVE COAT	SQ YD	29,415	29,415			
	42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	2,408	2,408			
	42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	23	23			
	42100800	PAVEMENT REINFORCEMENT 9"	SQ YD	2,408	2,408			
	44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	65,662	65,662			
	44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	193,845	193,845			
	44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	421,135	421,135			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	400	400			
	44000700	APPROACH SLAB REMOVAL	SQ YD	4,641	4,641			
	44001980	CONCRETE BARRIER REMOVAL	FOOT	412.5	412.5			
	44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	334	334			
	44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	30,300	30,300			
	44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SQ YD	339	339			
	44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	11,155	11,155			
	44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	132	132			
	44002218	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4 1/2"	SQ YD	19,416	19,416			
	44200537	CLASS A PATCHES, TYPE I, 9 INCH	SQ YD	231	231			
	44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	46	46			
	44200541	CLASS A PATCHES, TYPE II, 9 INCH	SQ YD	3,972	3,972			
	44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	20	20			
	44200545	CLASS A PATCHES, TYPE III, 9 INCH	SQ YD	1,332	1,332			
	44200583	CLASS A PATCHES, TYPE IV, 12 INCH	SQ YD	187	187			
	44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	23,628	23,628			
	44201748	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	234	234			
	44200549	CLASS A PATCHES, TYPE I, 10 INCH	SQ YD	335	335			
	44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	6,025	6,025			

** FOR LOCATIONS AND EXTENT OF WORK NOT SHOWN IN THE PLANS, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND CONTACT RICK WANNEE, ROADSIDE DEVELOPMENT ARCHITECT, IDOT ROADSIDE DEVELOPMENT UNIT AT (847) 705-4172 AT LEAST 72 HOURS PRIOR TO STARTING WORK.

NOTE A: SN 022-0092, SN 022-0094, SN 022-0095, SN 022-0096, SN 022-0097, SN 022-0098, SN 022-0099, SN 022-0100, SN 022-0104, SN 022-0105, SN 022-0111, SN 022-0112, SN 022-0137, SN 022-0138

FILE NAME =	DESIGNED - AJP	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN - TMB	REVISED -						2211, 1-1, 2&3RS-7	DUPAGE	546	3	
USER NAME = #USER#	CHECKED - JMM	REVISED -						*290,355	CONTRACT NO. 60G51			
PLOT DATE = #DATE#	DATE - 10/16/09	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
								SCALE: N.T.S.	SHEET NO. 1 OF 4 SHEETS	STA. TO STA.		