

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		SURVEILLANCE		BRIDGE		
					URBAN		SN 022-0101		SN 022-0102		
					90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	
					CONSTRUCTION TYPE CODE						
					1000-2A	Y032-1F	X211-2A	X271-2A			
44201767		CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	1,500	1,500						
44201761		CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	34	34						
44201769		CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	23,628	23,628						
44201765		CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	102	102						
44213000		PATCHING REINFORCEMENT	SQ YD	30,224	30,224						
44201769		CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	102	102						
44213200		SAW CUTS	FOOT	21,196	21,196						
44201771		CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	102	102						
44300300		STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	408,870	408,870						
48201037		HOT MIX ASPHALT SHOULDERS, 10"	SQ YD	23,065	23,065						
50102400		CONCRETE REMOVAL	CU YD	469.0				58.8		410.2	
50104650		SLOPE WALL REMOVAL	SQ YD	224						224	
50157300		PROTECTIVE SHIELD	SQ YD	21,739				2,136		19,603	
50200100		STRUCTURE EXCAVATION	CU YD	1,970						1,970	
50300225		CONCRETE STRUCTURES	CU YD	276.2				0.4		275.8	
50300255		CONCRETE SUPERSTRUCTURE	CU YD	1540.7				58.0		1490.3	
50300280		BRIDGE DECK GROOVING	SQ YD	31,946				2,714		29,232	
50300300		PROTECTIVE COAT	SQ YD	34,775				2,921		31,854	
50501110		STRUCTURAL STEEL REMOVAL	POUND	7,910						7,910	
50800205		REINFORCEMENT BARS, EPOXY COATED	POUND	363,740				10,570		353,170	
50800515		BAR SPLICERS	EACH	1,804				144		1,660	
51100100		SLOPE WALL 4 INCH	SQ YD	224						224	
51205200		TEMPORARY SHEET PILING	SQ FT	2,068						2,068	
52000110		PREFORMED JOINT STRIP SEAL	FOOT	2,239.5				275.5		1,964	
54213447		END SECTIONS 12"	EACH	9	9						
55039700		STORM SEWERS TO BE CLEANED	FOOT	600	600						
58700300		CONCRETE SEALER	SQ FT	71,231				10,178		61,053	
59100100		GEOCOMPOSITE WALL DRAIN	SQ YD	726						726	
60100945		PIPE DRAINS 12"	FOOT	345	345						
60109580		PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	932						932	
60208210		CATCH BASINS, TYPE C, TYPE 20 FRAME AND GRATE	EACH	2	2						
60300205		FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	123	123						
60247160		DRAINAGE STRUCTURES, TYPE 1 WITH TWO TYPE 20 FRAMES AND GRATES	EACH	1	1						
60300310		FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	123	123						
60500050		REMOVING CATCH BASINS	EACH	2	2						
60605000		COMBINATION CURB AND GUTTER, TYPE B-6.24	FOOT	400	400						
60500060		REMOVING INLETS	EACH	11	11						
63000001		STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	425	425						
63300230		REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	125	125						
63000005		STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	125	125						
60900115		TYPE B INLET BOX, STANDARD 609001	EACH	3	3						
63200305		STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	550	550						
60900215		TYPE C INLET BOX, STANDARD 609001	EACH	3	3						
64200105		SHOULDER RUMBLE STRIP	FOOT	153,458	153,458						
60900330		TYPE D INLET BOX, STANDARD 609001	EACH	6	6						
67100100		MOBILIZATION	L SUM	1	1						
60900515		CONCRETE THRUST BLOCKS	EACH	9	9						
70106800		CHANGEABLE MESSAGE SIGN	CAL MO	48	48						
70102550		TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	6	6						
70300220		TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	180,788	180,788						
70300230		TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	41,690	41,690						
70300240		TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	41,470	41,470						

* Specialty Items
 Δ - Non-participating

NOTE A: SN 022-0092, SN 022-0094, SN 022-0095, SN 022-0096, SN 022-0097, SN 022-0098, SN 022-0099, SN 022-0100, SN 022-0104, SN 022-0105, SN 022-0111, SN 022-0112, SN 022-0137, SN 022-0138

FILE NAME =	DESIGNED - AJP	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN - TMB	REVISED -							*	221, 1-1, 2&3RS-7	DUPAGE	546	4
USER NAME = #USER#	CHECKED - JMM	REVISED -							*290,355	CONTRACT NO. 60G51			
PLOT DATE = #DATE#	DATE - 10/16/09	REVISED -							FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
									SCALE: N.T.S.	SHEET NO. 2 OF 4 SHEETS	STA. TO STA.		

Rev.