

CONTRACT 60G51
BARRIER, GUARD RAIL, & CURB SCHEDULE

LOCATION				STEEL PLATE BEAM GUARD RAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	STEEL PLATE BEAM GUARDRAIL, TYPE B	CONCRETE BARRIER REMOVAL AND REPLACEMENT, SINGLE FACE	CONCRETE BARRIER REMOVAL AND REPLACEMENT, DOUBLE FACE	COMBINATION CURB AND GUTTER REMOVAL
ALIGNMENT	DIRECTION	SIDE	STATION	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
355		Center	23+50					25	
355	SB	Center	24+80					5	
355	SB	Center	25+00					5	
355	SB	Center	28+20					5	
355	SB	Center	28+50					5	
355	SB	Center	31+20					5	
355	SB	Center	33+40					10	
355	NB	R	34+50	125	125				
355		Center	40+00					5	
355	SB	Center	42+10	50	50				
355	NB	R	70+50	12.5		12.5			
355		Center	9+90					15	
355	NB	R	92+00	25	25				
355	NB	R	92+20	25	25				
355	NB	L	93+50	25		25			
355	NB RAMP	R							400
355	SB	Center	109+95					10	
355	SB	Center	110+20					15	
355	NB	Center	133+00					10	
355	NB	Center	133+00					10	
355		Center	153+80					10	
290	WB	Center	30+50	25	25				
290		Center	39+00					25	
290	RAMP	L	43+00	25	25				
290	WB	R	43+20				10		
290		Center	55+90					5	
290		Center	55+91					5	
290		Center	56+00					5	
290		Center	56+80					5	
290		Center	72+00					10	
290	WB	L	80+00	25	25				
290	WB	R	87+90				10		
290	WB	R	120+00				5		
290	EB	R	125+00	25		25			
290	EB	R	127+50	25	25				
290	EB	R	127+50	37.5		37.5			
290	EB	R	128+00	25		25			
290	WB	R	207+10	25	25				
290	EB	Center	208+00					15	
290	EB	Center	208+50					5	
290	WB	R	212+00				65		
290	WB	R	220+70				5		
290	WB	R	221+00				5		
290	WB	Center	225+10	25	25				
290	WB	R	228+00	25	25				
290		Center	229+30					10	
290	WB	Center	231+50	25	25				
290	WB	Center	234+50						
290		Center	247+00					5	
290		Center	286+10					5	
TOTAL				550	425	125	100	230	400

CONTRACT 60G51
TEMPORARY INFORMATION SIGNING - STAGE 1

STATION	LEGEND/DESCRIPTION	PANEL		PANEL
		COVER DIMENSIONS		COVER AREA
		WIDTH (FT)	HEIGHT (FT)	(SQ FT)
94+80	RAMP CLOSED	12.0	3.0	36.0
98+80	LEFT LANE	26.5	3.0	79.5
98+80	RIGHT LANE	11.0	3.0	33.0
110+00	COVER	2.0	2.0	4.0
110+00	RIGHT LANE	16.7	3.0	50.0
117+70	COVER	2.0	2.0	4.0
117+70	COVER	2.0	2.0	4.0
122+00	COVER	2.0	2.0	4.0
122+00	ARROW	2.0	2.0	4.0
12+40	ARROW	2.0	2.0	4.0
181+95	ARROW	14.5	2.5	36.3
28+40	COVER	2.0	2.0	4.0
14+95	COVER	2.0	2.0	4.0
22+50	COVER	2.0	2.0	4.0
32+50	COVER	2.0	2.0	4.0
N/A	290 2010 - REPAIR & - RESURFACING - THORNDALE TO DOWNTOWN - EXPECT DELAYS	17.0	9.0	612.0
N/A	355 2010 - REPAIR & - RESURFACING - ARMY TRAIL TO DOWNTOWN - EXPECT DELAYS	17.0	9.0	153.0
TOTAL				1040.0

CONTRACT 60G51
TEMPORARY INFORMATION SIGNING - STAGE 2

STATION	LEGEND/DESCRIPTION	PANEL		PANEL
		COVER DIMENSIONS		COVER AREA
		WIDTH (FT)	HEIGHT (FT)	(SQ FT)
98+80	RIGHT LANE	11.0	3.0	33.0
110+00	RIGHT LANE	16.7	3.0	50.1
181+95	ARROW	14.5	2.5	36.3
14+95	COVER	2.0	2.0	4.0
22+50	COVER	2.0	2.0	4.0
32+50	COVER	2.0	2.0	4.0
98+80	COVER	2.0	2.0	4.0
98+80	COVER	2.0	2.0	4.0
98+80	ARROW	2.0	2.0	4.0
110+00	COVER	2.0	2.0	4.0
117+10	COVER	2.0	2.0	4.0
162+97	IL 83 - ALL EXITS - KEEP RIGHT	13.0	10.0	130.0
179+89	IL 83 - ALL EXITS	12.5	7.5	93.8
236+82	IL 83 - ALL EXITS	12.5	7.5	93.8
256+96	IL 83 - ALL EXITS - KEEP RIGHT	13.0	10.0	130.0
TOTAL				599.0