



**SPECIAL WASTE**

THE PROPOSED SCOPE OF WORK INCLUDES EXCAVATION AND DISPOSAL OF BACKFILL MATERIAL FROM BEHIND THE EXISTING BRIDGE ABUTMENTS OF:

- I-355 SB OVER US 20 (LAKE ST) - SN 022-0111
- I-355 NB OVER US 20 (LAKE ST) - SN 022-0112
- I-355 NB OVER IL 53 (ROHLWING RD) - SN 0220137
- I-355 SB OVER IL 53 (ROHLWING RD) - SN 022-0138
- I-290 EB OVER CHURCH RD (W ABUTMENT ONLY) - SN 022-0099

EXCAVATED MATERIAL IS LOCATED WITHIN EXISTING ROADWAY LIMITS AND SHALL BE DISPOSED OF WITHIN IDOT RIGHT-OF-WAY AND WITHIN THE PROJECT LIMITS AS SHOWN ON THIS SHEET.

IN ADDITION, EXCAVATED MATERIAL FROM THE ADJACENT CONTRACT 60157 WILL BE DISPOSED OF WITHIN THE CONTRACT 60651 PROJECT LIMITS AS SHOWN ON THE PLAN. THE CONTRACTOR SHALL COORDINATE HIS DISPOSAL ACTIVITIES WITH THE CONTRACT 60157 CONTRACTOR. GRADING THE EXCAVATED MATERIAL FROM CONTRACT 60157 WILL BE INCLUDED IN CONTRACT 60651. FINAL SEEDING SHALL NOT TAKE PLACE UNTIL ALL EXCAVATED MATERIAL HAS BEEN PLACED.

THIS PROJECT HAS BEEN SIGNED OFF IN-HOUSE FOR SPECIAL WASTE. IF THE PROPOSED SCOPE OF WORK CHANGES OR IF ADDITIONAL ROW/TEMPORARY EASEMENTS ARE REQUIRED, PLEASE CONTACT THE ENVIRONMENTAL STUDIES UNIT AT EXTENSION 4101 TO DISCUSS ANY POTENTIAL IMPACTS.

FILE NAME =	DESIGNED - AJP	REVISED -
...prpIn.ABC.C1.355.gradingplan_01.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 11/16/2009	DATE - 10/16/09	REVISED -

**benesch**

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GRADING PLAN  
I-290 /I-355 INFIELD**

SCALE: 1"=50' SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	221, 1-1, 2&3RS-7	DUPAGE	546	102
*290,355		CONTRACT NO. 60651		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		