


SOUTHBOUND SIGN SCHEDULE

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1 (SQ FT)	REMOVE SIGN PANEL-TYPE 2 (SQ FT)	REMOVE SIGN PANEL-TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REMOVAL OF SIGN LIGHTING, NO SALVAGE (EACH)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)											
SB-WP-03	37+50	EXIT	6.0	5.0	6.0	5.0								30.0	36.0		
SB-PM-03A	38+50	W13-3 (30 MPH)	4.0	5.0	4.0	5.0		20.0					20.0				
SB-TR-04	41+50	I 355 SOUTH TOLLWAY - JOLIET - ST LOUIS	12.5	12.0	12.5	12.0			150.0					150.0			1.0
SB-TR-05	41+50	IL 64 - NORTH AVE - 2 1/4 MILES	14.5	10.5	14.5	10.5			152.3					152.3			1.0
SB-TR-06	41+50	ARMY TRAIL RD - EXIT ONLY	20.0	6.0	20.0	6.0			120.0					120.0			1.0
SB-GM-07	47+00	"ADDISON - BLOOMINGDALE - GLENDALE HTS - NEXT RIGHT"	8.0	7.0	9.0	7.0			56.0					63.0			
SB-TR-08	54+70	"LAST EXIT BEFORE - TOLLWAY - ARMY TRAIL RD - EXIT ONLY"	21.0	13.0	21.0	13.0			273.0					273.0			1.0
SB-TS-08A1	55+00	R3-4	4.0	4.0	4.0	4.0				1.0			16.0			18.0	
SB-TS-08A2	55+00	EXCEPT - AUTHORIZED - VEHICLES	4.0	2.7	4.0	2.7				1.0			10.6				
SB-GM-09	60+50	LAST EXIT - BEFORE TOLLWAY	17.0	5.0	17.0	5.0			85.0					85.0			
SB-CL-10	64+90	ARMY TRAIL RD - EXIT ONLY	20.0	6.0	20.0	6.0			120.0					120.0			1.0
SB-TS-10A	89+00	W4-3R	4.0	4.0	4.0	4.0				1.0			16.0			18.0	
SB-WP-10B	94+00	R2-1 (55 MPH)	4.0	5.0	4.0	5.0				1.0			20.0			18.0	
LS-BM-11*	94+80	TO I 290 - CHICAGO - ROCKFORD	12.5	14.0	12.5	14.0			175.0					175.0			1.0
SB-CL-12	96+50	ARMY TRAIL RD - EXIT 1 MILE	20.0	6.5	20.0	6.5			130.0					130.0			1.0
SB-WP-12A	102+00	W13-3 (25 MPH)	3.0	4.0	4.0	5.0				1.0			20.0			18.0	
SB-WP-13	117+00	EXIT	6.0	5.0	6.0	5.0				1.0			30.0			36.0	
SB-PM-14B	117+66	W4-1R	4.0	4.0	4.0	4.0				1.0			16.0				
SB-WP-14A	121+33	W4-3R	4.0	4.0	4.0	4.0				1.0			16.0			18.0	
SB-TR-14	122+00	I 355 SOUTH TOLLWAY - JOLIET	12.5	10.5	12.5	10.5			131.3					131.3			1.0
SB-TR-15	122+00	20 - LAKE ST - EXIT ONLY	14.0	10.5	14.0	10.5			147.0					147.0			1.0
SB-WP-16	127+20	EXIT	6.0	5.0	6.0	5.0				1.0			20.0			36.0	
SB-TS-17	128+69	W13-3 (25 MPH)	3.0	4.0	4.0	5.0				1.0						18.0	
SOUTHBOUND SUBTOTAL							0	20	1540	0	11	0	155	1637	162	54	9

MILE POST MARKER ASSEMBLY

DIRECTION	EACH
NORTHBOUND	5
SOUTHBOUND	5
EASTBOUND	24
WESTBOUND	24
TOTAL	58

\*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -	 <b>LIN ENGINEERING, LTD.</b> Consulting Engineers Chatham, Illinois    Wentzville, Illinois	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILEL*	DRAWN - SEW	REVISED -			* 22(1, 1-1, 2&3)RS-7	DUPAGE	661	550				
USER NAME = *USER*	CHECKED - FML	REVISED -			* 290,355	CONTRACT NO. 60G51						
PLOT DATE = *DATE*	DATE - 12/2009	REVISED -			FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT						
				SCALE: N.T.S.		SHEET NO. 4 OF 4 SHEETS		STA.	TO STA.			