SIGN DETAIL

1:75

NB-TR-08
STA. 98+80

SIGN NUMBER	Overhead – One Down Arrow
WIDTH x HGHT.	12'–0" x 11'–0"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

FONT:
(1) ClearviewHwy-5-W
(2) ClearviewHwy-5-W-R

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	19.5	80.3	45	36
ARDOWN	0	56.7	12	32	22

Panel Style: guide_exp_overhead.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

							LENGTH	SERIES/SIZE
E	A	S	T					ClearviewHwy-5-W
79.6	93	106.7	118.1				47.2	15,12
C	h	i	c	a	g	o		ClearviewHwy-5-W-R
23.9	40.7	56.5	64.4	77.9	93.2	109.3	97.8	16/13

FILE NAME =	DESIGNED - SEW	REVISED -	LIN ENGINEERING, LTD. Consulting Engineers Chatham, Illinois Westmont, Illinois	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIGNING DETAILS
$FILEL$	DRAWN - SEW	REVISED -			
USER NAME = $USER$	CHECKED - FML	REVISED -			
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -			SCALE: N.T.S. SHEET NO. 6 OF 71 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	22(1, 1-1, 2&3)RS-7	DUPAGE	661	588
* 290,355		CONTRACT NO. 60G51		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		