SIGN DETAIL

1:75

SB-GM-07
STA. 47+00

SIGN NUMBER	name		
WIDTH x HGHT.	9'-0" x 7'-0"		
BORDER WIDTH	2"		
CORNER RADIUS	11"		
MOUNTING	Overhead		
BACKGROUND	TYPE:	Reflective	
	COLOR:	Green	
LEGEND/BORDER	TYPE:	Reflective	
	COLOR:	White/White	



SYMBOL	ROT	X	Y	WID	HT

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																																								LENGTH	SERIES/SIZE
A	d	d	i	s	o	n																																			ClearviewHwy-5-W-R
28.3	37.3	45.3	53.4	57	63.8	72.2																																		49.4	86.5
B	l	o	o	m	i	n	g	d	a	l	e																														ClearviewHwy-5-W-R
9.9	18.2	22.4	30.4	38.8	50.2	54.5	62.2	70.3	78.1	86.1	90.2																													86.2	86.5
G	l	e	n	d	a	l	e		H	t	s																														ClearviewHwy-5-W-R
12.7	21.9	26.1	34.2	41.9	49.8	57.8	61.9	67.8	76	84	89.2																													81.6	86.5
N	E	X	T		R	I	G	H	T																																ClearviewHwy-5-W
6.1	18.3	26.9	37.2	44.4	55.4	66.3	71.9	84.1	94.7																															95.8	10

FILE NAME =	DESIGNED - SEW	REVISED -
$FILE$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 14 OF 71 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	22(1, 1-1, 2&3)RS-7	DUPAGE	661	596
* 290,355		CONTRACT NO. 60G51		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		