SIGN DETAIL

1:75

SB-TR-08
STA. 54+70

SIGN NUMBER	name	
WIDTH x HGHT.	21'-0" x 13'-0"	
BORDER WIDTH	2"	
CORNER RADIUS	12"	
MOUNTING	Overhead	
BACKGROUND	TYPE:	Reflective
	COLOR:	Green
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	Black,White/White

SYMBOL	ROT	X	Y	WID	HT
ARDOWN	0	103.8	5.2	32	22

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																	LENGTH	SERIES/SIZE
L	A	S	T		E	X	I	T		B	E	F	O	R	E			ClearviewHwy-5-W
36	45.5	59.3	70.7	79.3	92.5	102.7	116.4	122.3	130.9	144.1	157.4	169.1	179.9	195.3	208.4		180	12
T	O	L	L	W	A	Y												ClearviewHwy-5-W
81.3	93.1	108.5	119.3	129	147.1	160.2											89.4	12
A	r	m	y		T	r	a	i	l		R	d						ClearviewHwy-5-W-R
38.7	57.2	68.2	89.5	101.9	115.6	130.8	140.9	156.5	165	170	186	201.7					174.5	1613
E	X	I	T															ClearviewHwy-5-W
61.4	71.6	85.3	91.2														38.5	12
O	N	L	Y															ClearviewHwy-5-W
140.8	156.3	170.9	180.2														49.8	12

FILE NAME = $FILEL$	DESIGNED - SEW	REVISED -
	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING,LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 15 OF 71 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	22(1, 1-1, 2&3)RS-7	DUPAGE	661	597
*	290,355	CONTRACT NO. 60C51		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		