SIGN DETAIL

1:75

WB-BM-01
STA. 70+60

FONT:
(1) ClearviewHwy-5-W-R
(2) ClearviewHwy-5-W

SIGN NUMBER	name
WIDTH x HGHT.	19'-6" x 12'-0"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1-1100A-2-22-10D	0	51.5	71.8	39.3	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																																				LENGTH	SERIES/SIZE
E	X	I	T	4																																		ClearviewHwy-5-W
156.2	164.7	176.1	181	198.2																																	53.9	10,15
T	O																																					ClearviewHwy-5-W-R
23	30.4																																				14.8	8
S	O	U	T	H																																		ClearviewHwy-5-W
102.8	115.3	130.7	143.6	155.8																																	62.2	12
B	i	e	s	t	e	r	f	i	e	l	d		R	d																								ClearviewHwy-5-W-R
19.9	36.2	44.1	58.8	71.6	82.8	99	108.7	119.7	127.5	143.7	152	163.6	180.8	196.5																							188.1	16/13
1	M	I	L	E																																		ClearviewHwy-5-W
88.4	105.2	118.3	124.2	133.3																																	51.2	15,10

FILE NAME =	DESIGNED - SEW	REVISED -	LIN ENGINEERING,LTD. Consulting Engineers Chatham, Illinois Westmont, Illinois	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIGNING DETAILS
$FILE1$	DRAWN - SEW	REVISED -			
USER NAME = $USER$	CHECKED - FML	REVISED -			SCALE: N.T.S. / SHEET NO. 41 OF 71 SHEETS / STA. / TO STA.
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -			

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	22(1, 1-1, 2&3)RS-7	DUPAGE	661	623
* 290,355		CONTRACT NO. 60G51		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		