

CONTRACT 60G52
TEMPORARY INFORMATION SIGNING - STAGE 1

STATION	LEGEND/DESCRIPTION	PANEL		PANEL COVER AREA (SQ FT)
		COVER DIMENSIONS		
		WIDTH (FT)	HEIGHT (FT)	
468+05	TRAFFIC	1.5	7.2	10.8
482+30	TRAFFIC	1.5	7.2	10.8
505+00	ALL LANES	1.8	12.5	22.9
522+50	ALL LANES	1.8	12.5	22.9
546+40	ALL LANES	1.8	12.5	22.9
522+50	LEFT 1/4 MILE	1.8	12.5	22.9
546+40	LEFT 3/4 MILE	1.8	12.5	22.9
600+00	COVER	12.0	17.5	210.0
590+80	COVER	8.0	14.0	112.0
NA	2010 REPAIR & RESURFACING	9.0	17.0	153.0
482+30	COVER	8.0	14.0	112.0
468+05	COVER	10.0	17.0	170.0
482+30	COVER	10.0	17.0	170.0
496+20	COVER	2.5	3.3	8.3
505+00	COVER	2.0	2.0	4.0
505+00	ARROW	2.0	2.0	4.0
TOTAL				1079.4

CONTRACT 60G52
TEMPORARY INFORMATION SIGNING - STAGE 2

STATION	LEGEND/DESCRIPTION	PANEL		PANEL COVER AREA (SQ FT)
		COVER DIMENSIONS		
		WIDTH (FT)	HEIGHT (FT)	
795+00	HARLEM AVE EXIT ONLY	3.0	19.5	58.5
468+05	TRAFFIC	1.5	7.2	10.8
482+30	TRAFFIC	1.5	7.2	10.8
809+40	EXIT ONLY	2.5	18.0	45.0
836+30	EXIT ONLY	2.5	18.0	45.0
522+50	LEFT 1/4 MILE	1.8	12.5	22.9
546+40	LEFT 3/4 MILE	1.8	12.5	22.9
600+00	COVER	12.0	17.5	210.0
590+80	COVER	8.0	14.0	112.0
482+30	COVER	8.0	14.0	112.0
468+05	COVER	10.0	17.0	170.0
482+20	COVER	10.0	17.0	170.0
505+00	COVER	2.0	2.0	4.0
522+50	COVER	2.0	2.0	4.0
522+50	ARROW	2.0	2.0	4.0
TOTAL				1001.8

CONTRACT 60G52
TEMPORARY PAVEMENT MARKING AND TEMPORARY IMPACT ATTENUATOR SCHEDULE

STAGE	WET REFLECTIVE TEMPORARY TAPE - LETTERS AND SYMBOLS	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	TEMPORARY PAVEMENT MARKING - LINE 6"	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	EPOXY PAVEMENT MARKING - LINE 4 INCH	EPOXY PAVEMENT MARKING - LINE 8 INCH	EPOXY PAVEMENT MARKING - LINE 5 INCH	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	(SQ FT)	(FOOT)	(FOOT)		(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)
1		64,645	4,189	15,940	26,577	3,178	13,569					18	2		
2	109	77,132	15,524	22,264	16,420	719	16,732							2	13
RESURFACING		34,321	24,879		8,326	2,944		1,000	446,804	41,679	119,608				
TOTAL	109	176,098	44,592	38,204	51,323	6,841	30,301	1,000	446,804	41,679	119,608	18	2	2	13

FILE NAME =	DESIGNED - AJP	REVISED -
\\prp1n-abc.l2.sch.03.dgn	DRAWN - TMB	REVISED -
USER NAME = tbenk	CHECKED - JMM	REVISED -
PLDT DATE = 12/15/2009	DATE - 10/16/09	REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

F.A.I. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	13031.1, ETC., 383BRS-5	COOK	298	27
CONTRACT NO. 60G52				
SCALE: N.T.S.	SHEET NO. 3	OF 3 SHEETS	STA.	TO STA.
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				