SIGN DETAIL

1:75

EB-TR-82
STA. 741+70

SIGN NUMBER	name
WIDTH x HGHT.	18'-6" x 7'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)												LENGTH	SERIES-SIZE
L	E	F	T										ClearviewHwy-5-W
18	28.8	40.5	50.6									41.2	12
E	X	I	T	2	3	A							ClearviewHwy-5-W
70.1	80.4	94.1	100	118.6	133	147.1						91	12,15
A	u	s	t	i	n		B	l	v	d			ClearviewHwy-5-W-R
39.1	57.6	72.1	84.8	96.4	104.8	115.9	133.1	149.7	156.7	171.4		143.9	1613
L	E	F	T										ClearviewHwy-5-W
50.6	61.4	73.1	83.2									41.2	12
2	M	I	L	E	S								ClearviewHwy-5-W
106.9	127.1	140.3	146.2	155.2	164.2							64.6	15,10

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 26 OF 77 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3031.1, ETC., 383BIRS-5	COOK	413	354
		CONTRACT NO. 60G52		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		