SIGN DETAIL
1:75

EB-BM-92
STA. 862+60

SIGN NUMBER	name
WIDTH x HGHT.	16'-0" x 9'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

												LENGTH	SERIES-SIZE
E	X	I	T	2	3	B							ClearviewHwy-5-W
83	93.2	106.9	112.8	131.5	145.8	161.6						90	12,15
C	e	n	t	r	a	l		A	v	e			ClearviewHwy-5-W-R
22.5	38.7	54.9	69.4	81.3	91.3	107.3	112.3	126.5	143.1	157.8		147.1	16/13
R	I	G	H	T	¼	M	I	L	E				ClearviewHwy-5-W
29.4	42.5	49.1	63.8	76.5	97.2	128.2	141.3	147.2	156.3			133.3	12,15,10

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 35 OF 77 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3031.1, ETC., 3838)RS-5	COOK	413	363
		CONTRACT NO. 60G52		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		