


EASTBOUND SIGN SCHEDULE

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1 (SQ FT)	REMOVE SIGN PANEL-TYPE 2 (SQ FT)	REMOVE SIGN PANEL-TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REMOVAL OF SIGN LIGHTING, NO SALVAGE (EACH)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)											
EB-PM-105B	1057+17	W13-3 (30 MPH)	3.0	4.0	4.0	5.0											
EB-WP-106	1058+50	EXIT - 27A	7.5	5.0	7.0	5.0		12.0				20.0					
EB-BM-107	1064+30	EXIT 28A - DAMEN AVE - 1 MILE	15.5	8.0	15.5	8.0					1.0			35.0	36.0		
EB-BM-108	1064+30	EXIT 27C - WESTERN AVE - 1/4 MILE	17.0	8.0	17.0	8.0								124.0			1.0
EB-BM-108A*	1064+30	SACRAMENTO BLVD - 3000 W	10.6	2.5	10.6	2.5			124.0					136.0			1.0
EB-TS-108B	1070+46	TRUCKS - USE - 2 - RIGHT - LANES	4.0	5.0	4.0	5.0			26.5					26.5			
EB-BM-108C*	1077+65	CALIFORNIA AVE - 2800 W	9.1	2.5	9.1	2.5					1.0					18.0	
EB-CL-109	1083+10	EXIT 27C - WESTERN AVE - 2400 W	20.0	7.5	20.0	7.5		22.8				22.8					
EB-PM-109A	1083+10	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0				1.0
EB-WP-109B	1085+67	W4-1R	4.0	4.0	4.0	4.0							1.0		18.0		
EB-WP-110	1088+00	EXIT - 27C	7.5	5.0	7.0	5.0							1.0		36.0		
EB-WP-110A	1095+31	W4-1R	4.0	4.0	4.0	4.0							1.0		18.0		
EB-WP-110B	1096+00	W13-3 (30 MPH)	3.0	4.0	4.0	5.0							1.0		18.0		
EB-BM-110C	1090+79	14 FT 3 IN	5.5	1.5	5.5	1.5	8.3					8.3					
EB-WP-111	1096+90	EXIT	6.0	5.0	6.0	5.0							1.0		36.0		
EB-PM-111A	1103+91	R2-1 (55 MPH)	4.0	5.0	4.0	5.0		20.0					20.0				
EB-BM-112	1104+40	EXIT 28B - PAULINA ST-ASHLAND AVE - 3/4 MILE	32.0	7.5	32.0	7.5			240.0					240.0			1.0
EB-BM-113	1104+40	EXIT 28A - DAMEN AVE - 1/4 MILE	15.5	7.5	15.5	7.5			116.3					116.3			1.0
EB-BM-113A*	1104+40	WESTERN AVE - 2400 W	8.3	2.5	8.3	2.5		20.8					20.8				
EB-TS-113B1	1106+90	M3-2	2.5	1.3	2.5	1.3										18.0	
EB-TS-113B2	1106+90	M1-1-3 (I 290)	PER MUTCD STD (9FT ²)		PER MUTCD STD (9FT ²)												
EB-BM-113C*	1111+26	OAKLEY BLVD - 2300 W	8.0	2.5	8.0	2.5		20.0					20.0				
EB-WP-113D	1115+92	W4-1R	4.0	4.0	4.0	4.0							1.0		18.0		
EB-TS-113E*	1117+95	LEAVITT ST - 2200 W	6.6	2.5	6.6	2.5							1.0		18.0		
EB-BM-114	1118+00	EXIT 29A - RACINE AVE - 1 MILE	15.5	8.0	15.5	8.0			124.0					124.0			1.0
EB-BM-115	1118+00	EXIT 28B - PAULINA ST-ASHLAND AVE - 1/2 MILE	32.0	8.0	32.0	8.0			256.0					256.0			1.0
EB-BM-116	1118+00	EXIT 28A - DAMEN AVE - 2000 W	19.0	8.0	19.0	8.0			152.0					152.0			1.0
EB-PM-116A	1123+31	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					20.0				
EB-WP-117	1125+50	EXIT - 28A	7.5	5.0	7.0	5.0							1.0		36.0		
EB-PM-117A	1127+98	TRUCKS - USE - 2 - RIGHT - LANES	4.0	5.0	4.0	5.0		20.0					20.0				
EB-GM-118*	1130+50	ILLINOIS MED DISTRICT - UNIV OF ILL MED CENTER - RUSH UNIVERSITY - EXIT 28B	19.0	9.0	19.0	9.0			171.0					171.0			
EB-BM-118A*	1131+11	DAMEN AVE - 2000 W	7.5	2.5	7.5	2.5		18.8					1.0				
EB-WP-118B	1136+11	W4-1R	4.0	4.0	4.0	4.0			267.8				16.0		18.0		
EB-CL-119	1138+50	EXIT 28B - PAULINA ST 1700 W - ASHLAND AVE 1600 W	31.5	8.5	31.5	8.5								267.8			1.0
EB-BM-119A*	1139+45	OGDEN AVE - 1850 W	7.3	2.5	7.3	2.5		18.3					1.0				
EB-WP-119B	1144+14	W13-3 (30 MPH)	3.0	4.0	4.0	5.0							1.0		18.0		
EB-WP-120	1145+20	EXIT - 28B	7.5	5.0	7.0	5.0								35.0		36.0	
EB-PM-120A	1148+73	END - TRUCK - LANE - RESTRICTIONS	4.0	5.0	4.0	5.0		20.0					20.0				
EB-GM-121*	1149+50	UNIVERSITY - OF ILLINOIS - AT CHICAGO - EXIT 29A	13.0	10.0	13.0	10.0			275.0					130.0			
EB-BM-122	1151+20	90 94 KENNEDY EXPY RYAN EXPY - WISCONSIN - INDIANA - 1 MILE	25.0	11.0	25.0	11.0			124.0					171.0			1.0
EB-BM-123	1151+20	EXIT 29A - RACINE AVE - 1/2 MILE	15.5	8.0	15.5	8.0								124.0			1.0
EB-BM-123A*	1151+20	PAULINA ST - 1700 W	7.0	2.5	7.0	2.5		17.5					1.0				
EB-BM-123B*	1157+93	ASHLAND BLVD - 1600 W	8.6	2.5	8.6	2.5		21.5						21.5			
EB-WP-123C	1163+84	W4-1R	4.0	4.0	4.0	4.0								16.0		18.0	
EB-PM-123D1	1167+46	SPEED - ZONE - AHEAD	3.0	4.0	3.0	4.0								12.0			
EB-PM-123D2	1167+46	W13-1 (45 MPH)	2.0	2.0	2.0	2.0	4.0	12.0	146.3			4.0					
EB-BM-124	1170+30	EXIT 29A - RACINE AVE - 1200 W	19.5	7.5	19.5	7.5								146.3			1.0
EB-BM-124A*	1170+30	LOOMIS ST - 1400 W	6.8	2.5	6.8	2.5							1.0				
EB-PM-124B	1174+20	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0					1.0				
EB-WP-125	1175+20	EXIT - 29A	7.5	5.0	7.0	5.0								35.0		36.0	
EB-TS-125B1	1178+98	SPEED - ZONE - AHEAD	3.0	4.0	3.0	4.0								12.0			18.0
EB-TS-125B2	1178+98	W13-1 (45 MPH)	2.0	2.0	2.0	2.0				1.0			4.0				
EB-PM-125A1	1178+98	SPEED - ZONE - AHEAD	3.0	4.0	3.0	4.0											
EB-PM-125A2	1178+98	W13-1 (45 MPH)	2.0	2.0	2.0	2.0	4.0	12.0				1.0		4.0			
EB-WP-125C	1184+00	R2-1 (45 MPH)	4.0	5.0	4.0	5.0			171.0					20.0		18.0	
EB-PM-125D	1184+00	R2-1 (45 MPH)	4.0	5.0	4.0	5.0		20.0	201.3					20.0			
EB-BM-126*	1184+20	CONGRESS PKWY - CHICAGO LOOP	19.0	9.0	19.0	9.0			178.3								1.0
EB-BM-127*	1184+20	90 94 WEST KENNEDY EXPY - WISCONSIN	17.5	11.5	17.5	11.5											1.0
EB-BM-128*	1184+20	90 94 EAST RYAN EXPY - INDIANA	15.5	11.5	15.5	11.5											1.0
EB-BM-128A*	1184+20	RACINE AVE - 1200 W	7.4	2.5	7.4	2.5			18.6	162.8				18.6			
EB-BM-128B*	1198+41	MORGAN ST - 1000 W	7.0	2.5	7.0	2.5			17.5	187.0				17.5			
EB-BM-129	1204+80	90 94 WEST KENNEDY EXPY - WISCONSIN	15.5	10.5	16.5	10.5											1.0
EB-BM-130	1204+80	90 94 EAST RYAN EXPY - INDIANA	17.0	11.0	17.0	11.0			285.0					173.3			1.0
EB-BM-130A*	1204+80	PEORIA ST - 900 W	6.4	2.5	6.4	2.5		16.1	173.3				16.1				
EB-TR-131*	1208+20	CONGRESS PKWY - CHICAGO LOOP	30.0	9.5	30.0	9.5			187.0								1.0
EB-TR-132*	1208+20	90 94 WEST KENNEDY EXPY - WISCONSIN	16.5	10.5	16.5	10.5											1.0
EB-TR-133*	1208+20	90 94 EAST RYAN EXPY - INDIANA	17.0	11.0	17.0	11.0											1.0
EB-PM-133A	1208+20	R2-1 (45 MPH)	4.0	5.0	4.0	5.0		20.0	162.8				20.0				
EB-TS-133B	1210+38	R2-1 (45 MPH)	4.0	5.0	4.0	5.0			187.0				20.0				18.0
EB-TR-134	1210+50	90 94 WEST KENNEDY EXPY - WISCONSIN	15.5	10.5	16.5	10.5											1.0
EB-TR-135	1210+50	90 94 EAST RYAN EXPY - INDIANA	17.0	11.0	17.0	11.0											1.0
EB-BM-136	1211+18	LANES SPLIT	4.0	4.0	4.0	4.0			16.0					16.0			
EB-BM-137*	1211+18	HALSTED ST - 800 W	7.0	2.5	7.0	2.5			17.5					17.5			
EASTBOUND SUBTOTAL							29	642	6199	7	33	69	1110	6597	594	216	32

*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -	 <p>LIN ENGINEERING, LTD. Consulting Engineers Channah, Illinois Westmont, Illinois</p>	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	<p align="center">SCHEDULE OF QUANTITIES</p>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN - SEW	REVISED -						290	(2828B,D, ETC., 3031.1)RS-6	COOK	300	187
USER NAME - #USER#	CHECKED - FML	REVISED -						CONTRACT NO. 60653				
PLOT DATE - #DATE#	DATE - 12/2009	REVISED -						SCALE: N.T.S.	SHEET NO. 2 OF 4 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT	