SIGN DETAIL

1:75

WB-TR-105
STA. 895+10

SIGN NUMBER	name	
WIDTH x HGHT.	16'-6" x 10'-6"	
BORDER WIDTH	2"	
CORNER RADIUS	12"	
MOUNTING	Overhead	
BACKGROUND	TYPE:	Reflective
	COLOR:	Green
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	White/White

FONT:
(1) ClearviewHwy-5-W
(2) ClearviewHwy-5-W-R

SYMBOL	ROT	X	Y	WID	HT
M1-I100A-2-22-10D		6	45.5	39.3	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

										LENGTH	SERIES/SIZE
L	E	F	T								ClearviewHwy-5-W
18	28.8	40.5	50.6							41.2	12
E	X	I	T	2	1	A					ClearviewHwy-5-W
70.1	80.4	94.1	100	118.6	132.8	143.9				87.8	12,15
H	a	r	l	e	m		A	v	e		ClearviewHwy-5-W-R
49.3	65.8	81.8	92.8	101	117.2	135.3	150.7	167.3	182	144.5	16/13
L	E	F	T								ClearviewHwy-5-W
38.6	49.4	61.1	71.2							41.2	12
2	M	I	L	E	S						ClearviewHwy-5-W
91.8	112.1	125.3	131.2	140.2	149.2					64.6	15,10

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - SEW	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING,LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 38 OF 79 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(2828B,D, ETC., 3031.1)RS-6	COOK	300	251
		CONTRACT NO. 60G53		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		