

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAU 1321	0303 VB-I	COOK	21	5

CONTRACT NO.: 60H80

CONSTRUCTION TYPE CODE: SFTY - 2A *URBAN*

CODE NO.	ITEMS	UNITS	TOTAL QUANTITIES
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	90
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	21
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	21
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	56
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	695
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	437
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	10
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	10
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	695
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	16
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

**Specialty Items*

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES