SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: I000-2A 90% FED. 10% STATE	TRAF. SIG. Y031-1F 90% FED. 10% STATE	EVP Y031-3D 100% VILLAGE OF NORTH AURORA
35300600	PORTLAND CEMENT CONCRETE BASE COURSE 11"	SQ YD	229	229		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2		
40600300	AGGREGATE (PRIME COAT)	TON	0.8	0.8		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.4	0.4		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	10	10		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	47	47		
42001300	PROTECTIVE COAT	SQ YD	362	362		
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	371	371		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1108	1108		
44003100	MEDIAN REMOVAL	SQ FT	3669	3669		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	287	287		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1092	1092		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	953	953		
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	30	30		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12	12		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	15		15	
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109.2	109.2		
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2552	2552		
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	750	750		
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	65	65		
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	74	74		
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	28	28		
78300105	PAVEMENT MARKING REMOVAL	FOOT	2556	2556		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	17	17		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: I000-2A 90% FED. 10% STATE	TRAF. SIG. Y031-1F 90% FED. 10% STATE	EVP Y031-3D 100% VILLAGE OF NORTH AURORA
• 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	575		575	
• 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	5		5	
• 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	48		48	
• 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	10		10	
• 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	62		62	
• 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	266		266	
• 81400100	HANDHOLE	EACH	6		6	
• 81400200	HEAVY-DUTY HANDHOLE	EACH	2		2	
• 81400300	DOUBLE HANDHOLE	EACH	1		1	
• 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	633		633	
• 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2	
• 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1	
• 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1	
• 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	722			722
• 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1811		1811	
• 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	886		886	
• 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2147		2147	
• 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	76		76	
• 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1		1	
• 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1	
• 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1	
• 87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1		1	
• 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4	
• 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	15		15	
• 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	45		45	

• SPECIALTY ITEM

FILE NAME = c:\pw_work\pwidot\dbreuath\d0158873\P9119809-topoutgn
USER NAME = dbreuath
PLOT SCALE = 50.000 ' / IN.
PLOT DATE = 10/16/2009

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILL 31 / ILL 56 AT I-88 RAMP
SUMMARY OF QUANTITIES
SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	97-N-2	KANE	21	3
		CONTRACT NO. 60148		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT