

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT		TOTAL QUANTITIES	I000-2A 90% FED. 10% STATE	TRAF. SIG. Y031-1F 90% FED. 10% STATE	EVP Y031-3D 100% VILLAGE OF NORTH AURORA				CODE NO		ITEM	UNIT	TOTAL QUANTITIES	I000-2A 90% FED. 10% STATE	TRAF. SIG. Y031-1F 90% FED. 10% STATE	EVP Y031-3D 100% VILLAGE OF NORTH AURORA			
• 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	7		7																
• 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1																
• 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1																
• 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	3		3																
• 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2		2																
• 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10		10																
• 88500100	INDUCTIVE LOOP DETECTOR	EACH	9		9																
• 88600100	DETECTOR LOOP, TYPE I	FOOT	624		624																
• 88700200	LIGHT DETECTOR	EACH	4			4															
• 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1															
• 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1																
• 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	7647		7647																
• 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	575		575																
• 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1																
• 89502380	REMOVE EXISTING HANDHOLE	EACH	9		9																
• 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5		5																
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	77.1	77.1																	
• X0323412	REMOVE EXISTING SERVICE INSTALLATION	EACH	1		1																
• X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1																
• X0325890	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1		1																
• X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1																
• X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1		1																
• X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	2895		2895																
• X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	453		453																
• X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	722			722															

• SPECIALTY ITEM