SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY 90% FED 10% STATE COOK	ROADWAY 90% FED 10% STATE DUPAGE	SURVEILLANCE 90% FED 10% STATE COOK	SURVEILLANCE 90% FED 10% STATE DUPAGE	BRIDGE SN 016-1130 SN 016-1131 SN 016-1132 SN 016-1133 90% FED 10% STATE COOK	BRIDGE SN 022-0005 SN 022-0006 90% FED 10% STATE DUPAGE	BRIDGE SN 022-0007 SN 022-0008 90% FED 10% STATE DUPAGE	BRIDGE SN 016-0083 SN 016-0084 SN 016-1134 SN 016-1135 90% FED 10% STATE COOK
					CONSTRUCTION TYPE CODE							
					I000-2A	I000-2A	Y032-1F	Y032-1F	X171-2A	X231-2A	X271-2A	X271-2A
	50300260	BRIDGE DECK GROOVING	SQ YD	25,026					8,366	4,164	4,182	8,314
	50300300	PROTECTIVE COAT	SQ YD	26,343					8,732	4,349	4,582	8,680
	50501005	JACK AND REPOSITION BEARINGS	EACH	26						26		
	50501130	STRUCTURAL STEEL REPAIR	POUND	777					777			
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	161,670					9,240	131,860	11,430	9,140
	50800515	BAR SPLICERS	EACH	1,039					88	689	152	110
	51100100	SLOPE WALL 4 INCH	SQ YD	185					69		116	
	51205200	TEMPORARY SHEET PILING	SQ FT	625						625		
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	2,059.5					559.0	365.5	575.0	560.0
	54213447	END SECTIONS 12"	EACH	4		4						
Δ	55039700	STORM SEWERS TO BE CLEANED	FOOT	480	288	192						
	58700300	CONCRETE SEALER	SQ FT	47,089					13,732	12,451	7,340	13,566
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	187						187		
	60100945	PIPE DRAINS 12"	FOOT	80		80						
	60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	371						371		
	60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	5		5						
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5		5						
	60500060	REMOVING INLETS	EACH	4		4						
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,022	1,022							
	60900330	TYPE D INLET BOX, STANDARD 609001	EACH	4		4						
	60900515	CONCRETE THRUST BLOCKS	EACH	4		4						
*	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	75	75							
	63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	75	75							
	63300230	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	105		105						
	64200105	SHOULDER RUMBLE STRIP	FOOT	21,310	13,050	8,260						
	67100100	MOBILIZATION	L SUM	1	0.6	0.4						
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1		1						
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	46	31	15						
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	25,508	16,258	9,250						
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	16,920	3,837	13,083						
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	14,727	3,340	11,387						
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	100		100						
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	76,441	41,201	35,240						
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,876	360	1,516						
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,168	1,338	830						
*	78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	276	64	212						
*	78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	313		313						

Δ · Non-participating
* Specialty Items

FILE NAME =	DESIGNED - AJP	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
...\prpln_ABC_C4_soq_02.dgn	DRAWN - TMB	REVISED -				290	2009-099BR	COOK/DUPAGE	309 / 4
USER NAME = tblank	CHECKED - JMM	REVISED -						CONTRACT NO. 60I57	
PLOT DATE = 11/16/2009	DATE - 10/16/09	REVISED -			SCALE: N.T.S. / SHEET NO. 2 OF 3 SHEETS / STA. / TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

Rev.