SIGN DETAIL

1:75

WB-GM-45
STA. 395+40

FONT:
(1) ClearviewHwy-5-W-R
(2) ClearviewHwy-5-W

SIGN NUMBER	name
WIDTH x HGHT.	13'-6" x 9'-0"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	30.7	58	45	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)																																				LENGTH	SERIES/SIZE
T	O																																				ClearviewHwy-5-W-R
8	17.2																																			18.5	10
N	O	R	T	H																																	ClearviewHwy-5-W
88.1	105.3	120.7	132.6	144.8																																65.9	15,12
T	O	L	L	W	A	Y																															ClearviewHwy-5-W-R
83.1	92.3	104.5	112.9	120.4	134.9	145.2																														70.9	10
M	i	l	w	a	u	k	e	e																													ClearviewHwy-5-W-R
16.5	36	44.5	51.6	72.5	88.4	104.4	118.2	133.8																												129.1	16/13
E	X	I	T	1	3	A																															ClearviewHwy-5-W
40.2	50.4	64.1	70	88.7	100.1	114.2																														88.1	12,15

FILE NAME =	DESIGNED - SEW	REVISED -
⊕FILEL⊕	DRAWN - SEW	REVISED -
USER NAME = ⊕USER⊕	CHECKED - FML	REVISED -
PLOT DATE = ⊕DATE⊕	DATE - 12/2009	REVISED -

LIN ENGINEERING,LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 39 OF 58 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2009-099BR	COOK/DUPAGE	394	367
		CONTRACT NO. 60157		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		