SIGN DETAIL
1:75

WB-GM-46
STA. 402+30

SIGN NUMBER	name
WIDTH x HGHT.	13'-6" x 10'-0"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Ground
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

FONT:
(1) ClearviewHwy-5-W-R
(2) ClearviewHwy-5-W

SYMBOL	ROT	X	Y	WID	HT
M1-I100A-2-22-10D		40.8	72.9	39.3	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

									LENGTH	SERIES/SIZE
T	O									ClearviewHwy-5-W-R
18	27.2								18.5	10
E	A	S	T							ClearviewHwy-5-W
95.1	107.8	121.5	132.9						46.5	15,12
N	o	r	t	h		A	v	e		ClearviewHwy-5-W-R
18.7	36.4	53.2	62.6	74.5	85.5	101	117.5	132.3	125.3	16/13
E	X	I	T	1	3	A				ClearviewHwy-5-W
41	51.3	65	70.9	89.5	100.9	115.1			88.1	12,15

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 40 OF 58 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2009-099BR	COOK/DUPAGE	394	368
		CONTRACT NO. 60I57		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT