


PROPOSED DECK REHABILITATION AREAS



LEGEND

- DECK SLAB REPAIR PARTIAL
- DECK SLAB REPAIR (FULL DEPTH, TYPE II)
- DECK SLAB REPAIR (FULL DEPTH, TYPE I)

NOTES:

Deck Drains that are Located in Areas of Full Depth Repair Shall be Replaced as approved by the Engineer. Cost Included with Deck Slab Repair (Full Depth, Type I) or Deck Slab Repair (Full Depth, Type II) as Applicable.

The Areas of Deck Slab Repair are Based on Results of an Infrared Deck Survey Conducted on 04/16/09.

Areas of Deck Slab Repair (Partial) are shown for Information only to assist the Contractor in bidding.

Areas of repair that are located within 10 feet of the parapet face should be repaired in maximum lengths of 10' at a time to ensure stability of the parapet.

BILL OF MATERIAL

ITEM	UNIT	TOTAL
DECK SLAB REPAIR (FULL DEPTH, TYPE I)	Sq Yd	1
DECK SLAB REPAIR (FULL DEPTH, TYPE II)	Sq Yd	124

ILLINOIS DEPARTMENT OF TRANSPORTATION

SHEET TITLE

DECK SLAB REPAIR

PROJECT

I-55 NB OVER KANKAKEE RIVER
FAI ROUTE 55, SECTION 88(B&B-1)BR
WILL COUNTY
SN 099-0001

PROJECT NO. 03095-16
SCALE
DATE 6/25/09
DRAWN BY CFC
CHECKED BY MCB
DRAWING NO.

COOMBE-BLOXDORF P.C.
Engineers / Land Surveyors
Springfield, Illinois
Design Firm License No. 184-002703

8
OF 19 SHTS

PLOT DATE = 6/25/09
PLOT SCALE = 1" = 20'-0"
USER NAME = JAL