



**NOTES:**

Deck Drains that are Located In Areas of Full Depth Repair Shall be Replaced as approved by the Engineer. Cost Included with Deck Slab Repair (Full Depth, Type I) or Deck Slab Repair (Full Depth, Type II) as Applicable.

The Areas of Deck Slab Repair are Based on Results of an Infrared Deck Survey Conducted on 04/16/09.

Areas of Deck Slab Repair (Partial) are shown for Information only to assist the Contractor in bidding.

Areas of repair that are located within 10 feet of the parapet face should be repaired in maximum lengths of 10' at a time to ensure stability at the parapet.

**BILL OF MATERIAL**

ITEM	UNIT	TOTAL
DECK SLAB REPAIR (FULL DEPTH, TYPE I)	Sq Yd	4
DECK SLAB REPAIR (FULL DEPTH, TYPE II)	Sq Yd	114

**LEGEND**

- DECK SLAB REPAIR PARTIAL
- DECK SLAB REPAIR (FULL DEPTH, TYPE II)
- DECK SLAB REPAIR (FULL DEPTH, TYPE I)

ILLINOIS DEPARTMENT OF TRANSPORTATION

SHEET TITLE: DECK SLAB REPAIR

PROJECT	PROJECT NO.
I-55 NB OVER KANKAKEE RIVER FAI ROUTE 55, SECTION 88(B&B-1)BR WILL COUNTY SN 099-0001	03095-16
DRAWN BY	DATE
CFC	6/25/09
CHECKED BY	DRAWING NO.
MCB	9

**COOMBE-BLOXDORF P.C.**  
Engineers / Land Surveyors  
Springfield, Illinois  
Design Firm License No. 184-002703

OF 19 SHTS

PLOT DATE = 6/25/09  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = JML