

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY I000-1A	LANDSCAPING Y003	HIGHWAY ILLUMINATION Y030-1E	NON-PARTICIPATING
60600705	CONCRETE CURB, TYPE B (ABUTTING EXISTING PAVEMENT)	FOOT	540	540	-	-	-
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	541	541	-	-	-
67100100	MOBILIZATION	L SUM	1	1	-	-	-
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	-	-	-
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	-	-	-
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	-	-	-
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,290	6,290	-	-	-
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,097	2,097	-	-	-
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	25	25	-	-	-
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	65	65	-	-	-
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	650	290	-	-	360
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	942	757	-	-	185
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	172	32	-	-	140
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	-	-	-
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4	-	-	-
78300100	PAVEMENT MARKING REMOVAL	SQ FT	218	218	-	-	-
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	-	-	1	-
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	-	-	1	-
* 81000600	CONDUIT IN TRENCH, 2" DIA. GALVANIZED STEEL	FOOT	100	-	-	100	-
* 81018500	CONDUIT PUSHED, 2" DIA. GALVANIZED STEEL	FOOT	1,985	-	-	1,985	-
* 81603050	UNIT DUCT, 3*6 XLP, 1*8 XLP GROUND 1" POLYETHYLENE	FOOT	4,566	-	-	4,566	-
* 81702400	ELECTRICAL CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO.2	FOOT	140	-	-	140	-
* 81900200	TRENCH & BACKFILL FOR ELECTRICAL WORK	FOOT	2,581	-	-	2,581	-
* 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1	-	-	1	-
* 83600200	LIGHT POLE FOUNDATION, 24-INCH DIAMETER	FOOT	312	8	-	304	-
* 83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	39	1	-	38	-
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	757	757	-	-	-
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	-	-	-
△ Z0076600	TRAINEES	HOUR	500	500	-	-	-

* INDICATES SPECIALTY ITEM △ Y080

F.A.P. 352 ILLINOIS ROUTE 137 (SHERIDAN ROAD)

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 181-100569184-000000000000
48626
H:\WINHAR\0000002\0000\00000001\00000001\00000001.dwg



DESIGNED - MWP	REVISED - IDOT REVIEW 2/19/09
DRAWN - CJC	REVISED - IDOT REVIEW 4/22/09
CHECKED - MDW	REVISED - IDOT REVIEW 10/27/09
DATE - 8-1-08	REVISED - IDOT REVIEW 11/17/09

VILLAGE OF WINTHROP HARBOR, ILLINOIS ILLINOIS ROUTE 137 (SHERIDAN ROAD) AND 7th STREET STREETSCAPE IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
06-00036-00-LS	LAKE	70	6
FED. ROAD DIST. NO. 1		CONTRACT NO. 63167	
JOB NO. C-91-197-10		ILLINOIS FED. AID PROJECT ARA-000(IGI)	