



SEQUENCE OF CONSTRUCTION:

1. CLOSE EXISTING VALVE.
2. REMOVE EXISTING HYDRANT.
3. INSTALL HYDRANT EXTENSION AND NEW VALVE.
4. RELOCATE EXISTING HYDRANT.
5. OPEN EXISTING VALVE, REMOVE BOX.
6. BACKFILL.
7. FLUSH AND TEST FOR CHLORIDE RESIDUAL AND PROVIDE TEST.

ALL WORK TO BE DONE IN ACCORDANCE WITH ARTICLE 564 OF THE STANDARD SPECIFICATIONS. NEW VALVE AND BOX SHALL BE SAME MAKE AND MODEL AS EXISTING.

## FIRE HYDRANT TO BE MOVED

\* F.A.P. 352 ILLINOIS ROUTE 137 (SHERIDAN ROAD)  
ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME = W:\diststd\22x34\bd36.dgn	USER NAME = geglionobt	DESIGNED -	REVISED - R. SHAH 09-09-94	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>FIRE HYDRANT TO BE MOVED</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - R. SHAH 10-25-94			*	06-00036-00-LS	LAKE	70	54
		PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			<b>BD-36</b>			
		PLOT DATE = 1/4/2008	DATE -	REVISED -	SCALE: NONE	SHEET NO. 1	OF 1	SHEETS	STA.	TO STA.
						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-00D1(810)				