SUMMARY OF QUANTITIES

S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	PAVEMENT CONSTRUCTION TYPE CODE 1000		
	20101700	SUPPLEMENTAL WATERING	UNIT	1	1		
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	17	17		
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	17	17		
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	17	17		
	25200110	SODDING, SALT TOLERANT	SQ YD	389	389		
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	359	359		
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8204	8204		
	40600300	AGGREGATE (PRIME COAT)	TON	165	165		
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1307	1307		
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2813	2813		
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	41	41		
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3098	3098		
	42400800	DETECTABLE WARNINGS	SQ FT	550	550		
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	32815	32815		
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1037	1037		
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	41	41		
	44000600	SIDEWALK REMOVAL	SQ FT	3070	3070		
	44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	12	12		
	44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	185	185		
	44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	191	191		
	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	550	550		
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	36	36		
	60255500	MANHOLES TO BE ADJUSTED	EACH	68	68		
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	7	7		
	67100100	MOBILIZATION	L SUM	1	1		
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5000	5000		
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	264	264		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8828	8828		
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3282	3282		
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	407	407		
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	461	461		
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1875	1875		
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

* - INDICATES SPECIALTY ITEMS

GENERAL NOTES

1. BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
2. UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITY INFORMATION.
3. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
4. SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
5. ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
6. THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
7. ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE.