



PROPOSED EMERGENCY VEHICLE PREEMPTORS		
EMERGENCY VEHICLE PREEMPTORS	3	4
MOVEMENT	↘	→

*** SCHEDULE OF QUANTITIES**

ITEM	UNIT	QUAN
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	255
LIGHT DETECTOR	EACH	2
LIGHT DETECTOR AMPLIFIER	EACH	1
MODIFY EXISTING CONTROLLER	EACH	1
ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	255

* THIS PLAN IS FOR THE PURPOSE OF INSTALLING EMERGENCY VEHICLE PREEMPTION EQUIPMENT AS SHOWN PER PLAN INDICATED IN THE SCHEDULE OF QUANTITIES. ALL OTHER EQUIPMENT SHOWN SHALL BE DISREGARDED.

*** ADDED EV PREEMPTION LOCATION NO. 10**

FILE NAME = 0924-PLAN-14 - IDOT P03	USER NAME =	DESIGNED -- MRS	REVISED -- 10-13-09 *	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED EMERGENCY VEHICLE PREEMPTION 142ND STREET & LINCOLN AVENUE SCHEDULE OF QUANTITIES, CABLE PLAN, & SEQUENCE OF OPERATION			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	CHECKED -- PKB	REVISED --		1599/3593	09-00114-00-TL	COOK	43	31			
	PLOT DATE = 10-13-09	DRAWN -- PS	REVISED --		CONTRACT NO. 63317							
		CHECKED -- AG	REVISED --		SCALE: NTS	SHEET NO. 31 OF 43 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT ARA-9003(336)		