

SUMMARY OF QUANTITIES					PAVEMENT		CONSTRUCTION TYPE CODE	
S.I.	CODE NO.	PAY ITEM	UNIT	QUANTITY	1000			
	20101700	SUPPLEMENTAL WATERING	UNIT	1	1			
	21400100	GRADING AND SHAPING DITCHES	FOOT	2000	2000			
	25000110	SEEDING, CLASS 1A	ACRE	.25	.25			
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23			
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23			
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23			
	35800200	AGGREGATE BASE REPAIR	TON	43	43			
	40300700	PREPARATION OF BASE	SQ YD	185	185			
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1767	1767			
	40600300	AGGREGATE (PRIME COAT)	TON	23	23			
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	536	536			
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	743	743			
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	52	52			
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	8596	8596			
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	238	238			
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	354	354			
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	24	24			
	44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	8	8			
	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	74	74			
	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	39	39			
	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	253	253			
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	107	107			
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2			
	542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	66	66			
	55100100	STORM SEWER REMOVAL, 4"	FOOT	25	25			
	55100500	STORM SEWER REMOVAL, 12"	FOOT	42	42			
	60255500	MANHOLES TO BE ADJUSTED	EACH	1	1			
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	4	4			
	67100100	MOBILIZATION	L SUM	1	1			
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1455	1455			
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	205	205			
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	80	80			
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	27	27			
	X0301245	SHOULDER REMOVAL	SQ YD	911	911			
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	496	496			
	XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	303	303			
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
	XX008230	HOT-MIX ASPHALT DRIVEWAY PAVEMENT (SPECIAL)	SQ YD	39	39			
	XX008231	AGGREGATE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	115	115			

**GENERAL NOTES:**

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE. THIS TEMPORARY AGGREGATE SHALL BE INCLUDED IN THE COST OF THE CONTRACT.

\* - INDICATES SPECIALTY ITEMS