

SUMMARY OF QUANTITIES		CONSTRUCTION CODE		107TH ST. HARLEM AVE TO OAK PARK AVE.	HARLEM AVE. BRIDGE TO 116TH ST.	RIDGELAND AVE. BRIDGE TO 118TH PL.
		SFT Y-1B	UNIT	TOTAL		
ITEM		UNIT	TOTAL			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	14	8	6	
20101100	TREE TRUNK PROTECTION	EACH	21	21		
20101200	TREE ROOT PRUNING	EACH	21	21		
20200100	EARTH EXCAVATION	CU YD	800	573	99	127
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2500	767	893	966
25000100	SEEDING, CLASS 1	ACRE	0.56	0.17	0.19	0.20
25100630	EROSION CONTROL BLANKET	SQ YD	1859		893	966
28000400	PERIMETER EROSION BARRIER	FOOT	4096	2424	882	790
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	2290	1474	357	458
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	20610	13269	3217	4124
42400800	DETECTABLE WARNINGS	SQ FT	126	108	18	
44000100	PAVEMENT REMOVAL	SQ YD	211			211
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	228	216	12	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1		
60250900	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 5 FRAME, CLOSED LID	EACH	1	1		
60255500	MANHOLES TO BE ADJUSTED	EACH	5	1		4
60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2		
63300705	RUB RAIL	FOOT	1086		351	735
66400105	CHAIN LINK FENCE, 4'	FOOT	450		350	100
67100100	MOBILIZATION	L SUM	1			
70102620	TRAFFIC CONTROL & PROTECTION, STANDARD 701501	L SUM	1			
70102640	TRAFFIC CONTROL & PROTECTION, STANDARD 701801	L SUM	1			
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	905	728	177	
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	485	220		265
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	582	551		31
X2010510	CLEARING AND GRUBBING	L SUM	1			
XX006075	DEPRESSED CURB RAMP ACCESSIBLE TO THE DISABLED	SQ FT	955	907	48	
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	25	25		
XX004656	EMBANKMENT	CU YD	1000		400	600

* INDICATES SPECIALTY ITEM

PLOT DATE: Nov 05 2009
 FILENAME: H:\09-WO-3000\PLANS-ENG\REV-1\dwg\09-WO-3000-SITE PLAN 09-10-14.dwg

MORRIS ENGINEERING, INC.
 5100 S. LINCOLN SUITE 100 LISLE, ILLINOIS 60532
 PHONE: (630)271-0770 WEBSITE: ECIVIL.COM
 LOCATION: H:\09-WO\3000\PLANS-ENG\REV-1\dwg\09-WO-3000-SITE PLAN 09-10-14.dwg
 MORRIS JOB NO.: 09-WO-3000

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 VILLAGE OF WORTH
 SIDEWALK IMPROVEMENTS
 SUMMARY OF QUANTITIES

SCALE: VERT. NA
 HORIZ. NA
 DATE 10-06-2009

DRAWN BY CJS
 DESIGNED BY AS
 CHECKED BY NEK