

ITEM NO.	IDOT PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	NAPERVILLE ROAD (IL 38 TO IL 56)	NAPERVILLE ROAD (IL 56 TO LUCENT LN)	LEMONT ROAD	GARY AVENUE	FERRY ROAD	DIEHL ROAD
					100% ARA	100% ARA	100% ARA	100% ARA	100% ARA	100% ARA
					I000-2A	I000-2A	I000-2A	I000-2A	I000-2A	I000-2A
1	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	28268	8502	4198	7107	3741	4494	2226
2	40600300	AGGREGATE (PRIME COAT)	TON	565.5	130.0	84.0	142.0	75.0	90.0	44.5
3	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	29	7	4	7	4	5	2
4	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2042	0	0	2042	0	0	0
5	40600895	CONSTRUCTING TEST STRIP	EACH	4	0	0	3	0	1	0
6	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	657			657			
7	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7707	0	0	757	3074	3876	0
8	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	18769	6371	3789	6427	0	0	2182
9	42400800	DETECTABLE WARNINGS	SQ FT	96	24		48		24	
10	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	91750			9015	36593	46142	
11	44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	125936	65020	38658				22258
12	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	37790	0	0	37790	0	0	0
13	44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	24314	0	0	24314	0	0	0
14	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	940	110	0	605	45	130	50
15	44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	40			40			
16	44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	70			70			
17	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	100			100			
18	44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	87	0	0	55	32	0	0
19	44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	184	0	0	120	64	0	0
20	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	269	0	0	175	94	0	0
21	44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	145	60	40			45	
22	44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	290	120	85			85	
23	44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	415	175	115			125	
24	44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	25						25
25	44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	42						42
26	44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	65						65
27	44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	1480	360	235	330	190	250	115
28	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	13122	2400	450	7572	900	1050	750
29	46102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	14.0	0	0	8.4	5.6	0	0
30	50300300	PROTECTIVE COAT	SQ YD	206	25	0	135	10	29	7
31	60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	0	0	1	0	0	0
32	60255500	MANHOLES TO BE ADJUSTED	EACH	9	2	2	1	2	1	1
33	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	11	0	0	11	0	0	0
34	67100100	MOBILIZATION	L SUM	1	0.2	0.2	0.2	0.2	0.1	0.1
35	70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	0.0	0.0	8.0	0.0	0.0	0.0
36	70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.0	0.0	1.0	0.0	0.0	0.0
37	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.0	0.0	0.0	1.0	0.0	0.0

ITEM NO.	IDOT PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	NAPERVILLE ROAD (IL 38 TO IL 56)	NAPERVILLE ROAD (IL 56 TO LUCENT LN)	LEMONT ROAD	GARY AVENUE	FERRY ROAD	DIEHL ROAD
					100% ARA	100% ARA	100% ARA	100% ARA	100% ARA	100% ARA
					I000-2A	I000-2A	I000-2A	I000-2A	I000-2A	I000-2A
38	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.3	0.3	0.2	0.2	0.0	0.0
39	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.0	0.1	0.3	0.0	0.3	0.3
40	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.1	0.3	0.2	0.2	0.1	0.1
41	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18154	4431	2521	4665	2777	2541	1219
42	70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	4161	1321	234	650	390	947	619
43	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	126177	30172	22769	31729	20874	14136	6497
44	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	28558	7497	2689	3360	2141	8920	3951
45	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1431	55	0	1376	0	0	0
46	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	7944	2738	500	1920	1307	1175	304
47	70300280	TEMPORARY PAVEMENT MARKING LINE - 24"	FOOT	1973	640	175	250	196	554	158
48	78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	5779	1806	234	1226	390	1379	944
49	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	126177	30172	22769	31729	20874	14136	6497
50	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	28558	7497	2689	3360	2141	8920	3951
51	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1431	55	0	1376	0	0	0
52	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	7944	2738	500	1920	1307	1175	304
53	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1973	640	175	250	196	554	158
54	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	453	0	0	0	0	453	0
55	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3298	990	459	568	577	496	208
56	88600600	DETECTOR LOOP REPLACEMENT	FOOT	5991	1127	640	1898	398	1248	680
57	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1642	0	0	1642	0	0	0
58	44004400	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	3085	1220	0	395	150	1245	75
59	XX005462	CHANGEABLE MESSAGE SIGN	WEEK	32	6	4	6	4	8	4
60	XX006257	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	3298	990	459	568	577	496	208
61	Z0076600	TRAINEES	HOUR	1000	0	0	0	0	0	0
62	XX008130	DRAINAGE STRUCTURE S. TO BE CLEANED AND GRATED	EACH	12	2	2	2	2	2	2

△
△
△
△
△
△
△
△
△
△
△

△ SPECIALTY ITEMS
* Y080