

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	J000-2A	Y031-1F	Y030-1E	Y007
				ROADWAY	TRAFFIC SIGNALS	LIGHTING	RETAINING WALL
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	39620	39620			
42400800	DETECTABLE WARNINGS	SQ FT	1137	1137			
44000100	PAVEMENT REMOVAL	SQ YD	15730	15730			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	10798	10798			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2385	2385			
44000300	CURB REMOVAL	FOOT	736	736			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7428	7428			
44000600	SIDEWALK REMOVAL	SQ FT	11896	11896			
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	122	122			
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	62	62			
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	126	126			
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	162	162			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	648	648			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	648	648			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	162	162			
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1			
50104650	SLOPE WALL REMOVAL	SQ YD	283				283
50300225	CONCRETE STRUCTURES	CU YD	190				190
50300285	FORM LINER TEXTURED SURFACE	SQ FT	693				693
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	14670				14670
51100100	SLOPE WALL 4 INCH	SQ YD	46				46
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1			
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1			
54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	1	1			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	308	308			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	32	32			
550A0130	STORM SEWERS, CLASS A, TYPE 1 27"	FOOT	48	48			
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	16	16			
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	336	336			
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	41	41			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	962	962			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	24	24			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	580	580			
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	32	32			
55100300	STORM SEWER REMOVAL 8"	FOOT	34	34			

● SPECIALTY ITEM

FILE NAME = ...:\oad\sheet\2215_Sum_Quant.dgn	USER NAME = krk	DESIGNED - JAT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WRIGHT BOULEVARD SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 50.0000' / IN.	DRAWN - JAT	REVISED -			1351	06-00090-00-PV	COOK	137	5	
	PLOT DATE = 10/29/2009	CHECKED - DJK	REVISED -			CONTRACT NO. 63378					
		DATE - 10-16-09	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-M-8003809					
					SHEET NO. 2 OF 8 SHEETS						