

70300645 TEMPORARY PAINT PAVEMENT MARKING LINE 12"

FOOT	LOCATION
91	STA 209+85 TO STA 214+38 S1 YELLOW DIAGONALS @ 30'
27	STA 219+50 TO STA 223+13 S1 YELLOW DIAGONALS @ 30'
118	TOTAL

70300660 TEMPORARY PAINT PAVEMENT MARKING LINE 24"

FOOT	LOCATION
24	NB STOP S1 BELTLINE
24	SB STOP S1 BELTLINE
20	NB STOP S2 BELTLINE
20	SB STOP S2 BELTLINE
24	NB STOP S3 BELTLINE
24	SB STOP S3 BELTLINE
136	TOTAL

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
4	STA 210+44 TO STA 213+11 SHORT TERM
8	STA 234+26 TO STA 240+54 SHORT TERM
1	STA 240+00 TO STA 240+52 SHORT TERM
4	STA 207+67 TO STA 210+43 SHORT TERM
1	STA 210+43 TO STA 211+11 SHORT TERM
13	STA 213+11 TO STA 223+35 SHORT TERM
12	STA 223+91 TO STA 232+75 SHORT TERM
7	STA 238+09 TO STA 240+00 SHORT TERM
7	STA 208+48 TO STA 210+44 SHORT TERM
15	STA 210+44 TO STA 214+67 SHORT TERM
11	STA 214+67 TO STA 218+06 SHORT TERM
5	STA 218+06 TO STA 219+46 SHORT TERM
89	STA 219+46 TO STA 246+15 SHORT TERM
7	STA 208+48 TO STA 210+44 SHORT TERM
3	STA 210+44 TO STA 211+11 SHORT TERM
8	STA 215+67 TO STA 218+08 SHORT TERM
3	STA 218+08 TO STA 218+82 SHORT TERM
13	STA 219+46 TO STA 223+35 SHORT TERM
16	STA 223+91 TO STA 228+56 SHORT TERM
12	STA 229+13 TO STA 232+91 SHORT TERM
9	STA 214+74 TO STA 217+42 SHORT TERM
3	STA 218+06 TO STA 218+82 SHORT TERM
3	STA 217+42 TO STA 218+03 SHORT TERM
8	STA 215+67 TO STA 218+06 SHORT TERM
13	STA 219+46 TO STA 223+35 SHORT TERM
16	STA 223+91 TO STA 228+56 SHORT TERM
12	STA 229+13 TO STA 232+91 SHORT TERM
47	STA 232+91 TO STA 246+91 SHORT TERM
11	STA 214+74 TO STA 218+03 SHORT TERM
5	STA 208+71 TO STA 210+44 SHORT TERM
15	STA 210+44 TO STA 214+67 SHORT TERM
11	STA 214+67 TO STA 218+06 SHORT TERM
5	STA 218+06 TO STA 219+46 SHORT TERM
92	STA 219+46 TO STA 246+91 SHORT TERM
11	STA 214+74 TO STA 218+03 SHORT TERM
12	STA 210+44 TO STA 218+96 SHORT TERM
3	STA 219+23 TO STA 220+91 SHORT TERM
4	STA 1535 TO STA 1810 BELTLINE SHORT TERM
31	STA 1005 TO STA 1917 BELTLINE SHORT TERM
5	STA 1006 TO STA 1162 BELTLINE SHORT TERM
19	STA 1306 TO STA 1876 BELTLINE SHORT TERM
5	STA 1162 TO STA 1306 BELTLINE SHORT TERM
7	STA 1503 TO STA 1686 BELTLINE SHORT TERM
16	STA 1006 TO STA 1503 BELTLINE SHORT TERM
7	STA 1686 TO STA 1891 BELTLINE SHORT TERM
49	STA 398 TO STA 1891 BELTLINE SHORT TERM
20	STA 398 TO STA 1005 BELTLINE SHORT TERM
3	STA 1797 TO STA 1875 BELTLINE SHORT TERM
64.6	EB THRU/LT TRN LN PS1 LETTERS & SYMBOLS

70301000 WORK ZONE PAVEMENT MARKING REMOVAL (CONT.)

SQ FT	LOCATION
46.8	SB LT TRN LN S1 LETTERS & SYMBOLS
46.8	NB LT TRN LN S1 LETTERS & SYMBOLS
46.8	SB LT TRN LN S2 LETTERS & SYMBOLS
46.8	NB LT TRN LN S2 LETTERS & SYMBOLS
46.8	SB LT TRN LN S2 LETTERS & SYMBOLS
46.8	SB LT TRN LN S3 LETTERS & SYMBOLS
46.8	NB LT TRN LN S3 LETTERS & SYMBOLS
91.0	STA 209+85 TO STA 214+38 S1 12"
27.0	STA 219+50 TO STA 223+13 S1 12"
24	NB STOP BELTLINE S1 24"
24	SB STOP S1 24"
20	NB STOP BELTLINE S2 24"
20	SB STOP S2 24"
24	NB STOP BELTLINE S3 24"
24	SB STOP S3 24"
30	STA 208+77 TO STA 209+61 S1 4"
45	STA 209+02 TO STA 210+31 S1 4"
31	STA 208+69 TO STA 209+61 S1 4"
413	STA 210+31 TO STA 223+41 S1 4"
572	STA 223+81 TO STA 240+54 S1 4"
92	STA 237+75 TO STA 240+52 S1 4"
280	STA 237+75 TO STA 246+15 S1 4"
38	STA 208+69 TO STA 209+85 S1 4"
213	STA 211+41 TO STA 214+62 S1 4"
269	STA 214+62 TO STA 218+66 S1 4"
65	STA 219+50 TO STA 220+48 S1 4"
177	STA 220+48 TO STA 223+13 S1 4"
131	STA 224+12 TO STA 228+05 S1 4"
311	STA 209+85 TO STA 214+62 S1 4"
178	STA 220+48 TO STA 223+14 S1 4"
141	STA 224+12 TO STA 228+34 S1 4"
180	STA 229+34 TO STA 234+75 S1 4"
105	STA 215+50 TO STA 218+66 S1 4"
47	STA 219+50 TO STA 220+91 S1 4"
12	STA 1840 TO STA 1873 S1 4"
149	STA 1444 TO STA 1890 S1 4"
149	STA 1444 TO STA 1890 S1 4"
489	STA 1005 TO STA 1744 S1 4"
77	STA 1744 TO STA 1859 S1 4"
463	STA 1049 TO STA 1744 S1 4"
38	STA 1744 TO STA 1859 S1 4"
423	STA 210+44 TO STA 223+08 S2 4"
83	STA 224+09 TO STA 226+58 S2 4"
88	STA 208+49 TO STA 211+11 S2 4"
87	STA 235+95 TO STA 246+15 S2 4"
39	STA 208+49 TO STA 209+65 S2 4"
77	STA 208+49 TO STA 209+65 S2 4"
141	STA 209+65 TO STA 211+90 S2 4"
524	STA 211+90 TO STA 219+75 S2 4"
199	STA 219+75 TO STA 223+08 S2 4"
284	STA 224+09 TO STA 228+35 S2 4"
440	STA 229+35 TO STA 235+95 S2 4"
151	STA 209+65 TO STA 211+90 S2 4"
223	STA 219+75 TO STA 223+08 S2 4"
283	STA 224+09 TO STA 228+34 S2 4"
237	STA 229+34 TO STA 232+90 S2 4"
50	STA 228+65 TO STA 234+75 S2 4"
505	STA 208+49 TO STA 223+46 S2 4"
166	STA 223+73 TO STA 228+53 S2 4"
97	STA 1535 TO STA 1826 S2 4"
79	STA 1005 TO STA 1244 S2 4"
80	STA 1005 TO STA 1244 S2 4"
505	STA 1124 TO STA 1881 S2 4"
395	STA 1175 TO STA 1766 S2 4"
38	STA 1766 TO STA 1881 S2 4"
180	STA 398 TO STA 938 S2 4"
230	STA 1005 TO STA 1694 S2 4"
40	STA 1759 TO STA 1881 S2 4"
61	STA 1694 TO STA 1870 S2 4"
40	STA 1759 TO STA 1875 S2 4"
336	STA 213+11 TO STA 223+18 S3 4"

70301000 WORK ZONE PAVEMENT MARKING REMOVAL (CONT.)

SQ FT	LOCATION
85	STA 224+03 TO STA 226+57 S3 4"
85	STA 208+49 TO STA 211+00 S3 4"
38	STA 208+49 TO STA 209+62 S3 4"
491	STA 208+49 TO STA 223+19 S3 4"
591	STA 224+03 TO STA 232+90 S3 4"
101	STA 232+90 TO STA 235+95 S3 4"
483	STA 208+66 TO STA 223+19 S3 4"
388	STA 224+03 TO STA 229+86 S3 4"
288	STA 210+44 TO STA 218+96 S3 4"
60	STA 219+22 TO STA 220+91 S3 4"
105	STA 1535 TO STA 1847 S3 4"
73	STA 1005 TO STA 1891 S3 4"
590	STA 1005 TO STA 1891 S3 4"
590	STA 1005 TO STA 1891 S3 4"
38	STA 1776 TO STA 1891 S3 4"
47	STA 398 TO STA 938 S3 4"
33	STA 1796 TO STA 1891 S3 4"

16187 TOTAL

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
375	STA. 214+36.62 TO STA. 218+07.16 S1
625	STA. 215+09.94 TO STA. 221+34.12 S1
1000	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
675	STA. 214+60.12 TO STA. 221+34.04 S2
675	TOTAL

78008200 POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS

SQ FT	LOCATION
46.8	SB RT TRN LANE 3 RT ARROWS
46.8	SB LT TRN LANE 3 LT ARROWS
78	EB THRU/LT LANE 3 LT/THRU ARROWS
46.8	SB LT TRN LANE 3 LT ARROWS BELTLINE
15.6	NB RT TRN LANE 1 RT ARROW BELTLINE
46.8	NB LT TRN LANE 3 LT ARROWS BELTLINE
280.8	TOTAL

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -		742	34BR-1	WINNEBAGO	78	11				
		CHECKED -	REVISED -		CONTRACT NO. 64E68								
		DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			