

80% FED.
20% STATE

SUMMARY OF QUANTITIES			URBAN
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:	
		UNIT	I000 TOTAL ROADWAY
20200100	EARTH EXCAVATION	CU YD	25
* 25200110	SODDING, SALT TOLERANT	SQ YD	297
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2557
40600300	AGGREGATE (PRIME COAT)	TON	41
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5.2
40600535	LEVELING BINDER (HAND METHOD), N70	TON	8.7
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	448
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	450
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1625
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	248
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	7980
42400800	DETECTABLE WARNINGS	SQ FT	504
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	20290
44000600	SIDEWALK REMOVAL	SQ FT	7980
44001900	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	1202
60611600	COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	FOOT	1202
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1098
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	900
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	6258
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	244
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	1936
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	774
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	368
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1760
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3129
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	122
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	968
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	387
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	46
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24

80% FED.
20% STATE

SUMMARY OF QUANTITIES			URBAN
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:	
		UNIT	I000 TOTAL ROADWAY
88600100	DETECTOR LOOP, TYPE I	FOOT	716
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
X6025800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	12

* SPECIALTY ITEMS