

PAVEMENT										
LOCATION	SUB-BASE GRAN MATERIAL TY B 4"	HMA SHLDS 6 1/2"	HMA BASE COURSE 8"	BIT MAT PRIME COAT	LEVEL BINDER (MM) N50	HMA SURFACE COURSE MIX C N50	BRIDGE APPR PAVT CONN FLEXIBLE	AGG WEDGE SHLDS TYPE B	AGG SHLDS TYPE B 6"	TEMP RAMP
	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	SQ YD	TON	SQ YD	SQ YD
403+60 - 404+50				23	1.8	21.8		5	41	14.4
404+50 - 407+06	215.6	189.8	120.8	121	31.1	88.2			162	14.4
407+06 - 407+47	8.1	5.7	5.9				34.8			
408+23 - 408+65	8.1	5.8	5.7				34.8			
408+65 - 411+00	137.7	128.4	187.6	113.7	28.5	83.7			137	14.4
411+00 - 411+90				23	1.8	21.8		5	41	14.4
TOTAL	370	330	320	281	63	216	70	10	381	58

PAVEMENT REMOVAL			
LOCATION	PAVEMENT REMOVAL	APPROACH SLAB REMOVAL	HMA SURFACE REMOVAL BUTT JOINT
	SQ YD	SQ YD	SQ YD
403+60 - 404+20			174
407+06 - 407+26	60		
407+26 - 407+46		54	
408+23 - 408+43		54	
408+43 - 408+65	64		
411+30 - 411+90			174
STAGE 2			
404+33 - 405+07	144		
407+19 - 407+67	39		
408+37 - 408+83	36		
410+73 - 411+15	29		
STAGE 3			
404+22 - 404+95	59		
409+62 - 411+30	149		
TOTAL	580	108	348

EARTHWORK					
LOCATION	EARTH EXCAVATION	SUITABLE EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-)
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA. TO STA.					
403+60 - 407+44	108	54	41	69	28
408+27 - 411+90	60	30	23	38	15
TOTAL	168	84	64	107	43

STAGING ITEMS					
LOCATION	TEMPORARY CONCRETE BARRIER	REL TEMP CONCRETE BARRIER	IMPACT ATT TEMP (NON-RED) TEST LEVEL 3	IMPACT ATT REL (NON-RED) TEST LEVEL 3	TEMP PAVEMENT 8"
	FOOT	FOOT	EACH	EACH	SQ YD
PRE-STAGE 1					
404+33 - 405+07					144
407+19 - 407+67					39
408+37 - 408+83					36
410+73 - 411+15					29
STAGE 1					
406+06 - 409+72	370		2		
404+22 - 404+95					59
409+62 - 411+30					149
STAGE 2					
406+30 - 409+40		310		2	
TOTAL	370	310	2	2	456

NOTE 1: HMA BASE COURSE 8" CONSTRUCTED DURING PRE-STAGE 1 ALONG WITH TEMPORARY PAVEMENT
NOTE 2: SEE PAVEMENT REMOVAL SCHEDULE FOR REMOVAL OF TEMPORARY PAVEMENT

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwwork\pwwork\duncanbd\dms32420\d368833-sht-details.dgn	PLDT SCALE = 50,0000' / IN.	DRAWN -	REVISED -						41	(15BR-3)-1	LIVINGSTON	45	5
PLDT DATE = Oct 08, 2009 - 03:29:07 PM	CHECKED -	REVISOR -	REVISOR -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 66833				
	DATE -	REVISOR -	REVISOR -						ILLINOIS FED. AID PROJECT				