



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 23, 2009

SUBJECT: FAP Route 685 (IL 9)
Project ACBRF-0685 (030)
Section 37BR-1
McDonough & Fulton Counties
Contract No. 68352
Item No. 11, January 15, 2010 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheet 5 of the Plans.
3. Revised page 93 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Joseph E. Crowe, Region 3, District 4; Mike Renner; R. E. Anderson;
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0301512	GDRL AGG EROS CONT	TON	563.000				
X0323988	TEMP SOIL RETEN SYSTM	SQ FT	1,200.000				
X0712400	TEMP PAVEMENT	SQ YD	51.000				
X0919000	TEMP PAVT REMOVAL	SQ YD	51.000				
X2503100	MOWING	UNIT	64.000				
X4067107	POL LB MM IL4.75 N50	TON	343.000				
Z0001900	ASB BEARING PAD REMOV	EACH	22.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0030030	IMP ATTEN FRD NAR TL3	EACH	1.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	2.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	2.000				
Z0054500	ROCK FILL	TON	137.000				
* Z0076600	TRAINEES	HOUR	500.000		0.800		400.000
20100500	TREE REMOV ACRES	ACRE	1.300				
20200100	EARTH EXCAVATION	CU YD	14,378.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20200500	EARTH EXC WID	CU YD	2,304.000				
20201200	REM & DISP UNS MATL	CU YD	72.000				
20300100	CHANNEL EXCAV	CU YD	3,146.000				
20700220	POROUS GRAN EMBANK	CU YD	17.000				
20700400	POROUS GRAN EMB SPEC	CU YD	169.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	103.000				
21101615	TOPSOIL F & P 4	SQ YD	15,897.000				
25000210	SEEDING CL 2A	ACRE	3.500				
25000400	NITROGEN FERT NUTR	POUND	315.000				
25000500	PHOSPHORUS FERT NUTR	POUND	315.000				
25000600	POTASSIUM FERT NUTR	POUND	315.000				
25100115	MULCH METHOD 2	ACRE	3.500				
25100635	HD EROS CONTR BLANKET	SQ YD	5,870.000				
28000250	TEMP EROS CONTR SEED	POUND	700.000				
28000305	TEMP DITCH CHECKS	FOOT	336.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000400	PERIMETER EROS BAR	FOOT	6,481.000				
28000500	INLET & PIPE PROTECT	EACH	2.000				
28100107	STONE RIPRAP CL A4	SQ YD	515.000				
28100125	STONE RIPRAP CL B3	SQ YD	159.000				
28100811	STONE DUMP RIP CL A6	TON	1,570.000				
28200200	FILTER FABRIC	SQ YD	2,065.000				
31100300	SUB GRAN MAT A 4	SQ YD	1,086.000				
35501400	HMA BASE CSE VAR DP	TON	223.000				
35600716	HMA BC WID 10	SQ YD	974.000				
40200800	AGG SURF CSE B	TON	18.000				
40600215	P BIT MATLS PR CT	TON	9.400				
40600300	AGG PR CT	TON	31.000				
40600982	HMA SURF REM BUTT JT	SQ YD	160.000				
40600990	TEMPORARY RAMP	SQ YD	625.000				
40603335	HMA SC "D" N50	TON	692.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40800050	INCIDENTAL HMA SURF	TON	146.000				
42001430	BR APPR PVT CON (FLX)	SQ YD	43.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	39.500				
44000100	PAVEMENT REM	SQ YD	208.000				
44000152	HMA SURF REM 3/4	SQ YD	7,151.000				
44000200	DRIVE PAVEMENT REM	SQ YD	61.000				
44002720	GUTTER REMOV SPL	FOOT	2,379.000				
44201811	CL D PATCH T1 14	SQ YD	80.000				
44201815	CL D PATCH T2 14	SQ YD	206.000				
44201819	CL D PATCH T3 14	SQ YD	64.000				
44201821	CL D PATCH T4 14	SQ YD	217.000				
44300200	STRIP REF CR CON TR	FOOT	2,284.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	494.000				
48203029	HMA SHOULDERS 8	SQ YD	2,294.000				
50100100	REM EXIST STRUCT	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50104400	CONC HDWL REM	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	165.000				
50200100	STRUCTURE EXCAVATION	CU YD	244.000				
50300225	CONC STRUCT	CU YD	69.200				
50300255	CONC SUP-STR	CU YD	258.100				
50300260	BR DECK GROOVING	SQ YD	518.000				
50300280	CONCRETE ENCASEMENT	CU YD	5.600				
50300300	PROTECTIVE COAT	SQ YD	662.000				
50401105	F & E P P CON I-BM 54	FOOT	558.500				
50800105	REINFORCEMENT BARS	POUND	4,014.000				
50800205	REINF BARS, EPOXY CTD	POUND	62,950.000				
50800515	BAR SPLICERS	EACH	566.000				
51201600	FUR STL PILE HP12X53	FOOT	945.000				
51202305	DRIVING PILES	FOOT	945.000				
51203600	TEST PILE ST HP12X53	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
51500100	NAME PLATES	EACH	1.000				
54002020	EXPAN BOLTS 3/4	EACH	52.000				
54003000	CONC BOX CUL	CU YD	31.300				
54201273	P CUL 2 RCCP 18	FOOT	34.000				
54201297	P CUL 2 RCCP 42	FOOT	44.000				
54213663	PRC FLAR END SEC 18	EACH	1.000				
54213687	PRC FLAR END SEC 42	EACH	2.000				
54248510	CONCRETE COLLAR	CU YD	4.000				
550A0380	STORM SEW CL A 2 18	FOOT	79.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	107.000				
60100060	CONC HDWL FOR P DRAIN	EACH	3.000				
60107600	PIPE UNDERDRAINS 4	FOOT	2,293.000				
60109580	P UNDR FOR STRUCT 4	FOOT	148.000				
60219550	MAN TA 4 DIA T37G	EACH	2.000				
60600095	CLASS SI CONC OUTLET	CU YD	42.300				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60602600	CONC GUTTER TA MOD	FOOT	2,041.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	1,525.000				
63100085	TRAF BAR TERM T6	EACH	3.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	4.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	3.000				
63200310	GUARDRAIL REMOV	FOOT	2,449.000				
63300725	SPBGR (SHORT RADIUS)	FOOT	43.750				
66600105	FUR ERECT ROW MARKERS	EACH	34.000				
66700205	PERM SURV MKRS T1	EACH	11.000				
66700305	PERM SURV MKRS T2	EACH	1.000				
66700605	PERM SURVEY TIES	EACH	8.000				
67000400	ENGR FIELD OFFICE A	CAL MO	8.000				
67100100	MOBILIZATION	L SUM	1.000				
70100100	TRAF CONT-PROT 701316	EACH	1.000				
70100405	TRAF CONT-PROT 701321	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70100500	TRAF CONT-PROT 701326	L SUM	1.000				
70100600	TRAF CONT-PROT 701336	L SUM	1.000				
70101830	TRAF CONT-PROT BLR 21	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	120.000				
70106500	TEMP BR TRAF SIGNALS	EACH	1.000				
70106700	TEMP RUMBLE STRIP	EACH	6.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	1.000				
70300100	SHORT-TERM PAVT MKING	FOOT	976.000				
70300220	TEMP PVT MK LINE 4	FOOT	26,270.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	5,871.000				
70400100	TEMP CONC BARRIER	FOOT	387.500				
70400200	REL TEMP CONC BARRIER	FOOT	362.500				
78001110	PAINT PVT MK LINE 4	FOOT	9,764.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68352

State Job # - C-94-055-03
 PPS NBR - 4-00030-0100
 County Name - FULTON- MCDONOUGH-
 Code - 57 - 109 -
 District - 4 - 4 -
 Section Number - 37BR-1

Project Number
 ACBRF-0685/030/

Route
 FAP 685

* REVISED : DECEMBER 18, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78200410	GUARDRAIL MKR TYPE A	EACH	70.000				
78201000	TERMINAL MARKER - DA	EACH	8.000				
78300100	PAVT MARKING REMOVAL	SQ FT	3,255.000				
78300200	RAISED REF PVT MK REM	EACH	12.000				

Revise Article 280.07(f) of the Standard Specifications to read:

“(f) Temporary Mulch. This work will be measured for payment according to Article 251.05(b).”

Add the following paragraph after the ninth paragraph of Article 280.07 of the Standard Specifications:

“Temporary or permanent erosion control systems required for areas outside the limits of construction will not be measured for payment.”

Revise Article 280.08(b) of the Standard Specifications to read:

“(b) Temporary Ditch Checks. This work will be paid for at the contract unit price per foot (meter) for TEMPORARY DITCH CHECKS except for aggregate ditch checks which will be paid for at the contract unit price per ton (metric ton) for AGGREGATE DITCH CHECKS.”

Revise Article 280.08(f) of the Standard Specifications to read:

“(f) Temporary Mulch. Temporary Mulch will be paid for according to Article 251.06.”

Delete the tenth (last) paragraph of Article 280.08 of the Standard Specifications.

Revise the second sentence of the first paragraph of Article 1081.015(e) of the Standard Specifications to read:

“The upstream facing of the aggregate ditch check shall be constructed of gradation CA 3. The remainder of the ditch check shall be constructed of gradation RR 3.”

TRAFFIC BARRIER TERMINAL, TYPE 6 (BDE)

Effective: January 1, 2010

Delete the fourth paragraph of Article 631.07 of the Standard Specifications.

TRAINING SPECIAL PROVISIONS

This Training Special Provision supersedes Section 7b of the Special Provision entitled “Specific Equal Employment Opportunity Responsibilities,” and is in implementation of 23 U.S.C. 140(a).

As part of the contractor’s equal employment opportunity affirmative action program, training shall be provided as follows:

The contractor shall provide on-the-job training aimed at developing full journeyman in the type of trade or job classification involved. The number of trainees to be trained under this contract will be 1.

Revised 12/23/2009