

PAVEMENT MARKING REMOVAL				78300100
LOCATION/STATION		OFFSET	PAVEMENT MARKING REMOVAL	
FROM	TO		SQ FT	
242+21.85	244+31.50	CL	280	
248+71.50	249+00.00	CL	19	
249+00.00	253+03.00	CL	135	
242+21.85	243+00.00	RT	27	
242+21.85	243+00.00	LT	27	
243+00.00	243+65.75	RT	22	
243+00.00	243+65.75	LT	22	
243+66	24431.5	RT	22	
243+66	24431.5	LT	22	
248+72	24979.02	RT	36	
248+72	24970.59	LT	34	
249+79	25086.53	RT	36	
249+71	25144.83	LT	59	
250+87	25102.81	RT	6	
251+03	25124.05	RT	8	
251+24	25172.65	RT	17	
251+45	25218.47	LT	25	
251+73	25221.25	RT	17	
252+18	25303.12	LT	29	
252+21	25303	RT	28	
244+32	24871.5	CL	294	
244+32	24871.5	RT	147	
244+32	24871.5	LT	147	
	242+41.8	CL	11	
	242+61.8	CL	10	
	242+81.7	CL	9	
	243+1.6	CL	9	
	243+21.5	CL	7	
	243+41.4	CL	6	
	243+61.3	CL	4	
	243+81.3	CL	3	
	244+1.2	CL	1	
TOTAL			1519	

TEMPORARY PAVEMENT MARKING REMOVAL				70301000
LOCATION/STATION		STAGE	WORK ZONE PAVEMENT MARKING REMOVAL	
FROM	TO		SQ FT	
TEMPORARY PAVEMENT MARKINGS				
239+20.00	241+47.00	1	76	
241+47.00	250+36.00	1	297	
250+36.00	251+35.00	1	34	
240+47.00	241+47.00	2	34	
241+47.00	250+41.00	2	298	
250+41.00	252+47.00	2	34	
239+10		1	36	
240+52		1	28	
250+54		1	42	
250+61		1	28	
251+95		1	30	
239+87		2	36	
240+50		2	36	
250+54		2	38	
250+61		2	42	
252+57		2	30	
SHORT TERM PAVEMENT MARKINGS				
242+21.85	244+31.50		7	
244+31.50	248+71.50		15	
248+71.50	249+00.00		1	
249+00.00	253+03.00		14	
WINTER SHUTDOWN				
242+21.85	252+47.00		794	
TOTAL			1950.0	

TEMPORARY CONCRETE BARRIER			
		70400100	70400200
LOCATION/STATION		TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
FROM	TO	FOOT	FOOT
STAGE I			
241+50	250+12.5	862.5	
STAGE II			
248+71.50	250+06.80	25	862.5
TOTAL		887.5	862.5

DITCH CHECKS				28000315
ALIGNMENT	LOCATION/STATION	OFFSET	AGGREGATE DITCH CHECKS	
				TON
IL 47	244+32	60.5' LT	20	
IL 47	244+39	50' RT	20	
IL 47	248+66	74.5' RT	20	
IL 47	248+66	62' LT	20	
TOTAL				80

SIDEWALK					42400200
ALIGNMENT	LOCATION/STATION		OFFSET	WIDTH	PORTLAND CEMENT CONCRETE SIDEWALK, 5
					SQ FT
	FROM	TO			
IL 47	243+10.50	243+50.00	RT	5'	198
IL 47	243+50.00	244+31.50	RT	5'	408
IL 47	248+71.50	250+06.80	RT	5'	676
IL 47	250+06.80	250+35.90	RT	5'	146
IL 47	250+35.60	250+81.00	RT	5'	227
TOTAL					1654

LANDSCAPING								
LOCATION (STATION)		25000210	25000314	28000250	25100630	25000400	25000500	25000600
FROM	TO	SEEDING, CLASS 2A	SEEDING, CLASS 4B	TEMPORARY EROSION CONTROL SEEDING	EROSION CONTROL BLANKET	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
		ACRE	ACRE	POUND	SQ YD	POUND	POUND	POUND
242+50	243+00	0.002		0.198	10	0	0	0
243+00	243+50	0.015		1.518	73	1	1	1
243+50	244+00	0.020		1.980	96	2	2	2
249+00	249+50	0.066		6.600	319	6	6	6
249+50	250+00	0.066		6.600	319	6	6	6
250+00	250+50	0.066		6.600	319	6	6	6
250+50	251+00	0.066		6.600	319	6	6	6
251+00	251+50	0.016		1.584	77	1	1	1
251+50	252+00	0.007		0.660	32	1	1	1
252+00	252+50	0.007		0.660	32	1	1	1
246+50	248+05		0.500	50.000	2420			
TOTAL		0.33	0.50	83.00	4018.00	30.00	30.00	30.00
USE		0.50						

EARTHWORK AND FURNISHED EXCAVATION					
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE *	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	LOCAL SHARE FOR SIDEWALK
	CU YD	CU YD	CU YD	CU YD	CU YD
Sta. 242+50 to 243+00	12	9		+9	
Sta. 243+00 to 243+50	15	11		+12	
Sta. 243+50 to 244+00	21	15		+16	
Sta. 244+00 to 244+50			9	-9	
Sta. 249+00 to 249+50			513	-263	-250
Sta. 249+50 to 250+00			368	-148	-220
Sta. 250+00 to 250+50	2	2	196	-85	-110
Sta. 250+50 to 251+00	2	2	58	-57	
Sta. 251+00 to 251+50			33	-33	
Sta. 251+50 to 252+00			12	-12	
Sta. 252+00 to 252+50			5	-5	
Sta. 252+50 to 253+00					
Total	50	38	1193	-575	-580

\* SHRINKAGE FACTOR = 25%

FILE NAME = c:\pwworking\pwworking\STULTS\JM\01289950\0570428-shit-schedule rev.dgn



1170 SOUTH HOUBOLT ROAD  
JOLIET, ILLINOIS 60431  
(815) 744-4200  
USER NAME = stultsjw  
PLOT SCALE = 40.0000' / IN.  
PLOT DATE = 10/23/2009

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -  
REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(137BR)BR	CHAMPAIGN	75	9
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 70428	