

TRENCH BACKFILL

LOCATION	STATION	OFFSET	CU YD
RUNAROUND	18+02.07	LT&RT	22
RUNAROUND	18+08.80	LT&RT	21
RUNAROUND	18+15.49	LT&RT	21
TOTAL			64

TEMPORARY DITCH CHECKS

STATION	OFFSET	FOOT
384+25	LT	10
384+50	RT	10
392+00	LT	10
393+00	RT	10
15+00	RT	10
16+00	LT	10
16+00	RT	10
17+00	LT	10
17+00	RT	10
18+50	LT	10
19+50	LT	10
20+50	LT	10
21+50	LT	10
21+50	RT	10
22+50	RT	10
23+50	RT	10
TOTAL		160

PERIMETER EROSION BARRIER

LOCATION	STATION TO	STATION	OFFSET	FOOT
US 136	385+80.00	386+20.00	LT	40
US 136	386+60.00	387+60.00	LT	100
RUNAROUND	18+50.00	24+00.00	RT	550
TOTAL				690

STONE RIPRAP, CLASS A4

LOCATION	STATION TO	STATION	OFFSET	SQ YD
US 136	384+50.00	386+00.00	LT	167
US 136	385+50.00	387+25.00	RT	194
US 136	389+00.00	390+50.00	LT	167
US 136	390+50.00	392+00.00	RT	167
TOTAL				695

FILTER FABRIC

LOCATION	STATION TO	STATION	OFFSET	SQ YD
US 136	384+50.00	386+00.00	LT	167
US 136	385+50.00	387+25.00	RT	194
US 136	389+00.00	390+50.00	LT	167
US 136	390+50.00	392+00.00	RT	167
TOTAL				695

SUB-BASE GRANULAR MATERIAL, TYPE A, 4"

LOCATION	STATION TO	STATION	SQ YD
US 136	385+60.00	391+96.00	1979

AGGREGATE SURFACE COURSE, TYPE B

LOCATION	STATION TO	OFFSET	SQ FT	TON
US 136	381+88.00	RT	374	14
US 136	383+42.00	LT	300	11
US 136	393+89.00	LT	660	25
US 136	396+48.00	RT	287	11
TOTAL			1621	61

AGGREGATE FOR TEMPORARY ACCESS

LOCATION	STATION	OFFSET	TON
US 136	381+88.00 FE	RT	14
US 136	383+42.00 FE	LT	11
US 136	393+89.00 FE	LT	25
US 136	396+48.00 FE	RT	11
TOTAL			61

BITUMINOUS MATERIALS (PRIME COAT)

LOCATION	STATION TO	STATION	OFFSET	GALLON
US 136	383+40.00	393+48.00	LT&RT	3081
US 136	381+00.00	398+00.00	LT&RT	491
TOTAL				3572

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

LOCATION	STATION TO	STATION	SQ YD
US 136	381+00.00	382+00.00	289
US 136	396+00.00	398+00.00	578
TOTAL			867

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50

LOCATION	STATION TO	STATION	OFFSET	TON
US 136	383+40.00	385+60.00	LT&RT	280
US 136	385+60.00	391+96.00	LT&RT	1235
US 136	391+96.00	393+48.00	LT&RT	194
TOTAL				1709

HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50

LOCATION	STATION TO	STATION	OFFSET	TON
US 136	381+00.00	398+00.00	LT&RT	550

BITUMINOUS MATERIALS (PRIME COAT)

LOCATION	STATION	OFFSET	GALLON
FE US 136	393+89.00	LT	44

INCIDENTAL HOT-MIX ASPHALT SURFACING

LOCATION	STATION	OFFSET	TON
FE US 136	393+89.00	LT	10

PAVEMENT REMOVAL

LOCATION	STATION TO	STATION	OFFSET	SQ YD
US 136	386+50.00	386+99.00	LT&RT	142

APPROACH SLAB REMOVAL

LOCATION	STATION TO	STATION	OFFSET	SQ YD
US 136	386+83.62	386+99.54	LT	18
US 136	386+83.62	386+99.54	RT	18
US 136	388+26.27	388+42.19	LT	18
US 136	388+26.27	388+42.19	RT	18
TOTAL				72

PAVED DITCH REMOVAL

LOCATION	STATION TO	STATION	OFFSET	FOOT
US 136	384+44.00	385+70.00	LT	126
US 136	385+00.00	386+47.00	RT	147
US 136	388+94.00	392+81.00	LT	387
US 136	389+52.00	392+81.00	RT	329
TOTAL				989

PAVEMENT BREAKING

LOCATION	STATION TO	STATION	OFFSET	SQ YD
US 136	385+60.00	386+50.00	LT&RT	260
US 136	388+26.00	391+96.00	LT&RT	1069
TOTAL				1329

AGGREGATE SHOULDERS, TYPE B 6"

LOCATION	STATION TO	STATION	OFFSET	SQ YD
RUNAROUND	11+40.00	25+77.00	RT	479
RUNAROUND	12+46.00	24+60.00	LT	405
US 136	381+00.00	383+79.00	LT	93
US 136	383+79.00	390+33.00	LT	363
US 136	390+33.00	398+00.00	LT	256
US 136	381+00.00	383+95.00	RT	98
US 136	383+95.00	391+50.00	RT	419
US 136	391+50.00	398+00.00	RT	217
TOTAL				2330

PIPE CULVERT REMOVAL

LOCATION	STATION TO	STATION	OFFSET	FOOT
US 136	383+33.00	383+56.00	LT	23
US 136	396+33.00	396+65.00	RT	32
TOTAL				55

PIPE CULVERTS, CLASS D, TYPE 1 72" (TEMPORARY)

LOCATION	STATION TO	STATION	OFFSET	FOOT
RUNAROUND	17+93.01	18+11.13	LT&RT	70
RUNAROUND	17+99.74	18+17.86	LT&RT	70
RUNAROUND	18+06.47	18+24.50	LT&RT	70
TOTAL				210

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6' POSTS

LOCATION	STATION TO	STATION	OFFSET	FOOT
US 136	384+75.00	389+37.50	LT	462.5
US 136	384+91.50	390+54.00	RT	562.5
TOTAL				1025.0