

SUMMARY OF QUANTITIES (SHEET 1 OF 2)

LOCATION OF WORK: FAP 725 (IL 10 - SPRINGFIELD AVE.)
 URBAN
 MULTILANE
 CHAMPAIGN COUNTY
 STA. 320+09.70 TO 366+38.17
 MATTIS AVE. TO PROSPECT AVE. IN CHAMPAIGN

FUNDING BREAKOUT: FEDERAL - 100%
 CONSTRUCTION TYPE CODE: I000

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,485.9
40600300	AGGREGATE (PRIME COAT)	TON	43.4
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	652.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	1,450.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SQ YD	1,500.0
40600990	TEMPORARY RAMP	SQ YD	78.7
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COARSE, MIX "D", N90	TON	2,281.1
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	300.0
40800030	AGGREGATE (PRIME COAT)	TON	6.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	250.0
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	14,277.0
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	5,836.6
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	23.0
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	16.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3.0
67100100	MOBILIZATION	L SUM	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0

FILE NAME = c:\pwork\PM100T\HOGANBJ\d0142445\057782.sht-500.dgn	USER NAME = hoganbj	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1/8" = 40.0000' / IN.	CHECKED - ---	REVISED - ---	725			(32R, 2)RS-4	CHAMPAIGN	35	4	
PLOT DATE = 10/19/2009	DATE - ---	REVISED - ---	CONTRACT NO. 70782							
						SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____	