

S.B.I. RTE. 4	SECTION (L-15D) B	COUNTY MACOUPIN	TOTAL SHEETS 21	SHEET NO. 6
STA. 1605+99.63		TO STA. 1625+33.72		
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				

EARTHWORK				
LOCATION				EARTH EXCAVATION
				CY
LT & RT	1614+00.00	TO	1616+48.00	75
LT & RT	1616+48.00		1616+92.00	80
LT & RT	1616+92.00		1619+00.00	115
TOTAL				270

SEEDING										
LOCATION		SEEDING CLASS 2	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	AGRICULTURAL GROUND LIMESTONE		
		ACRES	POUND	POUND	POUND	POUND	ACRE	TON		
LT	1614+00.00	1618+81.33	0.1	10	9.0	9.0	9.0	0.1	0.2	
RT	1614+00.00	1619+00.00	0.1	10	9.0	9.0	9.0	0.1	0.2	
TOTAL			0.2	20	18.0	18.0	18.0	0.2	0.4	

PAVING SUMMARY								
LOCATION		PAVEMENT REMOVAL	AGGREGATE SHOULDERS, TYPE B 8"	PORTLAND CEMENT CONCRETE PAVEMENT 8"	GRANULAR CULVERT BACKFILL	WELDED WIRE FABRIC 6x6		
	TO	SY	SY	SY	CY	SY		
LT&RT	1614+50.00	1615+00.00	0	56	0	0	0	0
LT&RT	1615+00.00	1615+32.00	0	50	0	0	0	0
LT&RT	1615+32.00	1615+82.00	0	78	0	0	0	0
LT&RT	1615+82.00	1616+48.00	0	103	0	0	0	0
LT&RT	1616+48.00	1616+92.00	40	34	113	54	113	
LT&RT	1616+92.00	1617+57.00	0	101	0	0	0	0
LT&RT	1617+57.00	1618+07.00	0	78	0	0	0	0
LT&RT	1618+07.00	1618+31.33	0	38	0	0	0	0
LT&RT	1618+31.33	1618+81.33	0	56	0	0	0	0
TOTAL			40	592	113	54	113	

PIPE CULVERT			
LOCATION		PIPE CULVERTS, CORRUGATED STEEL, 15"	PIPE CULVERT REMOVAL
		FOOT	FOOT
RT	1615+00.00	179	
LT	1615+50.00	129	
RT	1615+79.61		15
LT	1615+93.27		20
RT	1617+52.20		15
RT	1618+00.00	134	
TOTAL		442	50

GUARDRAIL IMPROVEMENT SCHEDULE							
LOCATION		SPBGR TYPE A	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL	TRAFFIC BARRIER TERMINAL TYPE 6	GUARDRAIL MARKERS TYPE A	TERMINAL MARKERS DIRECT APPLIED	
	TO	FEET	EACH	EACH	EACH	EACH	
RT	1615+32.00	1616+59.00	50	1	1	1	1
LT	1615+82.00	1616+59.00	0	1	1	1	1
RT	1616+81.00	1617+57.00	0	1	1	1	1
LT	1616+81.00	1618+07.00	50	1	1	1	1
TOTAL			100	4	4	4	4

FENCING				
LOCATION			WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	
			FOOT	
LT	1615+58.00	TO	1617+17.00	160
TOTAL			160	

ENGINEER'S FIELD OFFICE TYPE B	
LOCATION	CAL MO
JOBSITE	6
TOTAL	6

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

PAVEMENT MARKINGS			
LOCATION			PAINT PAVEMENT MARKING SOLID YELLOW 5"
STATION	TO	STATION	FOOT
1615+32.00		1618+07.00	550
TOTAL			550

SILICONE JOINT SPECIAL	
LOCATION	FOOT
1616+59.00	16
1618+81.00	16
TOTAL	32

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NO SCALE
DATE:

DRAWN BY PRL
CHECKED BY JDR