CONTRACT NO. 72291

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SB14	(L-15D)B	MACOUPIN	21	11
STA. 1614+50		TO STA.1681+81.33		
FED. ROAD DIST. NO. 6	ILLINOIS	FED. AID PROJECT		

Girard

Nilwood

35 36 31 32 33 34

2 1 6 5 4 3

11 12 7 8 9 10

14 13 18 17 16 15

23 24 19 20 21 22

HENRY RD.

CAMBRIDGE RD.

PICKERELL LN.

IL RTE 4

GREEN RIDGE RD.

BROKER LN.

BETTIS RD.

OLD IL. 4
1950 E. RD

BENSTEAD RD.

1750 S. RD

RUTTLEDGE RD.

WYLDER RD.

WAGGONER RD.

20

28

PROJECT BEGINS
STA 1614+50

PROJECT ENDS
STA 1618+81.33

① ROAD CLOSED AHEAD — W20-3 (A) 48 W/ TYPE A FLASHER

② TYPE 3 BARRICADE W/ R11-2 AND TYPE A FLASHERS STANDARD 701901

③ ROAD CLOSED TO THRU TRAFFIC — R11-4

④ ROAD CLOSED 500 FT — W20- 3(O) 48

NOTES:

1) ALL ADVANCE WARNING ORANGE SIGNS SHALL BE 48" IN SIZE WHILE OTHER SIGNS SHALL BE 36" IN SIZE.

2) USE STD BLR 21

N

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL PLAN

SCALE: VERT. NONE
HORIZ. NONE

DATE

DRAWN BY PRL

CHECKED BY JLB

c:\pw_work\PWIDOT\LAUGHLINRL\dms27299\Detourplan_IDOT_REV.dgn
Oct-19-2009 01:53:32PM laughlinrl