

SUMMARY OF QUANTITIES

ILLINOIS DEPARTMENT OF TRANSPORTATION							
SUMMARY OF QUANTITIES							
LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	<i>80% FED. 20% STATE</i> TOTAL QUANTITY	ROADWAY 1000	STRUCTURE Y007		
28100207	STONE DUMPED RIPRAP, CLASS A4	TON	3,150	3,150			
28200200	FILTER FABRIC	SQ YD	4,430	4,430			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	79	79			
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	<i>1,978</i>	<i>1,978</i>			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	<i>6.2</i>	<i>6.2</i>			
40600300	AGGREGATE (PRIME COAT)	TON	<i>40.5</i>	<i>40.5</i>			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	229	229			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	187	187			
40600990	TEMPORARY RAMP	SQ YD	50	50			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	<i>362</i>	<i>362</i>			
44000100	PAVEMENT REMOVAL	SQ YD	<i>524</i>	<i>524</i>			
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	100	100			
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	100	100			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	60	60			

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
o:\pvc_work\PIWIDOT\LAUGHLINRL\0169540\0169540.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Oct-21-2009 11:02:51AM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
325	114 (B-1)	MACOUPIN	57	4
CONTRACT NO. 72646			ILLINOIS FED. AID PROJECT	

Rev.