

SUMMARY OF QUANTITIES

ILLINOIS DEPARTMENT OF TRANSPORTATION							
SUMMARY OF QUANTITIES							
LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	<i>80% FED. 20% STATE</i> TOTAL QUANTITY	ROADWAY 1000	STRUCTURE Y007		
50100300	REMOVAL OF EXISTING STRUCTURE NO. 1	EACH	1		1		
50100400	REMOVAL OF EXISTING STRUCTURE NO. 2	EACH	1	1			
50100500	REMOVAL OF EXISTING STRUCTURE NO. 3	EACH	1	1			
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2			
50105220	PIPE CULVERT REMOVAL	FOOT	23	23			
50800105	REINFORCEMENT BARS	POUND	34,440		34,440		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,240		1,240		
50800515	BAR SPLICERS	EACH	92		92		
54003000	CONCRETE BOX CULVERTS	CU YD	225.7		225.7		
54200640	PIPE CULVERTS, TYPE 1, <i>CORRUGATED STEEL OR ALUMINUM</i> CULVERT PIPE 15"	FOOT	52	52			
54201285	PIPE CULVERTS, TYPE 2 RCCP 30"	FOOT	69	69			
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5.4	5.4			
60602500	CONCRETE GUTTER, TYPE A	FOOT	188	188			
63200310	GUARDRAIL REMOVAL	FOOT	116	116			