

SCHEDULE OF QUANTITIES

FENCE, BARRIERS AND GUARDRAIL SCHEDULE								
STATION	WOVEN WIRE FENCE REMOVAL	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	GUARDRAIL REMOVAL	TEMP. TRAF. BAR. TERMINAL, TYPE 1, SP (TAN)	TEMPORARY CONCRETE BARRIER	RELOCATE CONCRETE BARRIER	IMPACT ATTENUATOR, TEMPORARY (FULLY-REDIRECTIVE NARROW), TEST LEVEL 3	IMPACT ATTENUATOR, RELOCATE (FULLY-REDIRECTIVE NARROW), TEST LEVEL 3
	(FOOT)	(FOOT)	(FOOT)	(EACH)	(FOOT)	(FOOT)	(EACH)	(EACH)
IL ROUTE 16								
STA. 806+20, 4' RT							1	
STA. 806+20, 4' LT								1
STA. 806+20 TO STA. 808+00					180	180		
STA. 807+20, 40' RT TO STA. 808+17, 41' RT	98							
STA. 808+00, TO STA. 809+50					150	150		
STA. 808+35 TO STA. 808+85, LT.				1				
STA. 807+96, 20' RT TO STA. 808+49, 20' RT			53					
STA. 808+17, 120' LT TO STA. 808+19, 51' LT	69							
STA. 808+19, 51' LT TO STA. 808+88, 51' LT	69							
STA. 808+85 TO STA. 809+60, LT.		75						
STA. 808+67, 42' RT TO STA. 810+60, 50' RT	193							
STA. 809+06, 20' LT TO STA. 809+69, 19' LT			63					
STA. 809+60 TO STA. 810+10, LT.				1				
STA. 809+44, 43' LT TO STA. 809+58, 52' LT	17							
STA. 809+58, 52' LT TO STA. 813+00, 52' LT	342							
STA. 809+50, TO STA. 811+00					150	150		
STA. 811+00, 4' RT							1	
STA. 811+00, 4' LT								1
TOTALS	788	75	116	2	480	480	2	2
USE	788	75	116	2	487.5	487.5	2	2

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS		
STATION	OFFSET	R-O-W MARKERS
		(EACH)
IL ROUTE 16		
STA. 805+50.00	40.00' LT	1
STA. 806+00.00	70.00' LT	1
STA. 806+00.00	40.00' RT	1
STA. 806+50.00	110.00' RT	1
STA. 807+25.00	70.00' LT	1
STA. 807+75.52	120.00' LT	1
STA. 808+15.64	120.00' LT	1
STA. 809+00.00	110.00' RT	1
STA. 810+50.00	50.00' RT	1
STA. 810+50.00	120.00' LT	1
STA. 811+00.00	70.00' LT	1
STA. 812+50.00	70.00' LT	1
STA. 813+00.00	50.00' LT	1
TOTALS		13

TREE REMOVAL SCHEDULE	
LOCATION	TREE REMOVAL, ACRES
ACRE	
IL ROUTE 16	
STA. 803+50 TO STA. 814+00	3.5
TOTAL	3.5

ESTIMATED QUANTITIES		
PAY ITEM	UNIT	QUANTITY
(*) MULCH, METHOD 2	ACRE	1.5
EARTH EXCAVATION FOR EROSION CONTROL	CU YD	20
TEMPORARY EROSION CONTROL SEEDING	POUND	400
AGGREGATE DITCH CHECKS	TON	80
PERIMETER EROSION BARRIER	FOOT	150
AGGREGATE (EROSION CONTROL)	TON	59
TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	2,400
GROUT FOR USE WITH RIPRAP	CU YD	19

(*) ESTIMATED QUANTITY FOR TEMPORARY EROSION CONTROL.

EROSION CONTROL SCHEDULE		
LOCATION	STONE DUMPED RIPRAP, CLASS A4	FILTER FABRIC
		(SQ YD)
IL ROUTE 16		
STA. 808+12 TO STA. 810+00, LT		
STA. 810+00 TO STA. 811+50, LT		
STA. 806+00 TO STA. 810+60, RT	1,827	2,569
STA. 808+20 TO STA. 812+00, LT.	1,321	1,858
STA. 807+35, 35' LT.		
STA. 807+77, 76' LT.		
STA. 808+75, 75' LT.		
STA. 809+65, 85' LT.		
STA. 809+80, 100' LT.		
STA. 810+10, 100' LT.		
STA. 807+50, 80' RT.		
STA. 809+20, 65' RT.		
STA. 811+10, 25' RT.		
TOTALS	3,148	4,427
USE	3,150	4,430