

SUMMARY OF QUANTITIES

CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	STP			ROADWAY RESURFACING
				RDWY. WIDENING F.A.P. 662 80% FEDERAL 20% STATE	ROADWAY F.A.P. 662 80% FEDERAL 20% STATE	STRUCTURE S.N. 059-7004 80% FEDERAL 20% STATE	PARKING LANES 50% STATE 50% VILLAGE
				CONSTRUCTION TYPE CODE			CONSTRUCTION TYPE CODE
				1000-2A	1000-2A	X028-2A	Y025
60264100	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 15 FRAME AND LID	EACH	2		2		
60605000	COMBINATION CONCRETE CURB AND GLITTER, TYPE B-6.24	FOOT	99	91	8		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2		2		
63200310	GUARDRAIL REMOVAL	FOOT	137.5		137.5		
64200105	SHOULDER RUMBLE STRIP	FOOT	27772	1170	26602		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	10		10		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12		12		
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	2	2		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3808	392	3416		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	404	281	123		
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	62328	9194	53134		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	78	78			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	84	18	66		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	28181	4363	23818		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	850		850		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	850		850		
70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25		25		
70500500	TEMPORARY STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	12.5		12.5		
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	16729	9174	7555		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	78	78			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	18	18			
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	404	281	123		
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	4300	20	4280		
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	66		66		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	364	108	256		
* 78200455	BIDIRECTIONAL GUARD RAIL REFLECTORS	EACH	2		2		

\*Specialty Items

Rev.