

SUMMARY OF QUANTITIES				US 24				IL 99			
				ROADWAY 90% FED 10% STATE STA 13+78 TO STA 31+77 SAFETY	ROADWAY 80% FED 20% STATE NHS	PARKING LANES 50% STATE 50% CITY	PARKING LANES 100% CITY	TRAFFIC SIGNALS 90% FED 10% STATE SAFETY	TRAFFIC SIGNALS 80% FED 15% STATE 5% CITY NHS	ROADWAY 80% FED 20% STATE STP	PARKING LANES 50% STATE 50% CITY
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE							
				I000-2A	I000-2A	I000-2A	I000-2A	Y031-1F	Y031-1F	I000-2A	I000-2A
20200100	EARTH EXCAVATION	CU YD	835	212	602					21	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	2,905	1,159	1,737					9	
20400800	FURNISHED EXCAVATION	CU YD	235		22					213	
20800150	TRENCH BACKFILL	CU YD	705	390	315						
25000200	SEEDING, CLASS 2	ACRE	2.75	1.00	1.50					0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	243	80	131					32	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	243	80	131					32	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	243	80	131					32	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	5.4	1.8	2.9					0.7	
25100125	MULCH, METHOD 3	ACRE	2.75	1.00	1.50					0.25	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	810	267	435					108	
28000305	TEMPORARY DITCH CHECKS	FOOT	76		76						
28000500	INLET AND PIPE PROTECTION	EACH	77	38	32					7	
28100207	STONE RIPRAP, CLASS A4	TON	58		58						
28200200	FILTER FABRIC	SQ YD	134		87					47	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	991	865	126						
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	6,775	2,505	4,270						
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	98	47	51						
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	288	128	160						
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	719	385	135					199	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	796	700	96						
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SQ YD	3,873	1,217	2,656						
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	570	211	359						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29.4	6.0	13.5	0.7	0.3			8.7	0.2
40600300	AGGREGATE (PRIME COAT)	TON	141	31	68	4	1			36	1
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	937	427	439					71	
40600895	CONSTRUCTING TEST STRIP	EACH	2		2						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	183	83						100	
40600990	TEMPORARY RAMP	SQ YD	668	53	351					264	

FILE NAME =
c:\pwwork\p\10107\LAUGHLIN\l\dm20175\4572660-shr-000.dgn

USER NAME = laughlin
PLOT SCALE = 40.0000' / IN.
PLOT DATE = Oct-07-2009 07:55:50AM

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SCALE: SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
* 7(W-1,RS-8,N); 9RS-4 BROWN 177 3
CONTRACT NO. 72B60
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT
* FAP 317 (115 24) & 450 (11 99)

Rev.