

LOCATION OF WORK	NHF 80% FEDERAL 20% STATE	100% ESP	NHF 80% FEDERAL 10% STATE 10% CITY*	100% ESP	NHF 80% FEDERAL 10% STATE 10% CITY	50% STATE 50% CITY	NHF 80% FED. 20% STATE LIGHTING
	ROADWAY VETERANS PARKWAY WASHINGTON ST LAWRENCE AVE	ROADWAY OLD JACKSONVILLE RD, MONROE ST	TRAFFIC SIGNALS @ IL 4 & MONROE ST/OLD JACKSONVILLE RD	TRAFFIC SIGNALS CLOCKTOWER DR	TRAFFIC SIGNALS WASHINGTON & LAWRENCE	SIDEWALK AT WASHINGTON ST AND LAWRENCE AVE	
	STA 274+00 TO STA 365+50	*ARRA ELIGIBLE TO MAX OF \$2.174M FED FUNDS, THEN CITY (MFT) FUNDS					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000	1000	Y031-1F	Y031-1F	Y031-1F	SFTY-1B	Y030-1E
81400100	HANDHOLE	EACH	9			7	2			
81400300	DOUBLE HANDHOLE	EACH	3			2	1			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	7,051			1,186	911			4,954
82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	6			6				
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2					2		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2			1	1			
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1			1				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1			1				
87100160	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24F	FOOT	926				926			
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2,166			1,551	615			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,644			2,001	643			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,255			1,778	477			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	5,304			4,338	966			
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	1,673			1,084	589			
87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	37				37			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	107			37	70			
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	2			2				
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	8			4	4			
87600200	PEDESTRIAN PUSH-BUTTON POST, TYPE II	EACH	2			2				
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1				1			
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2				2			
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1				1			
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1			1				
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1			1				



JOB = 2200.4	DESIGNED - NAK	REVISED -
FILE NAME = D672899-sh-t-S00.dgn	DRAWN - AJH	REVISED -
PLOT SCALE = 48.0000 "/ IN.	CHECKED - NAK	REVISED -
PLOT DATE = Oct-29-2009 09:07:56AM	DATE - 10/15/2009	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	10
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 72B99	