

TREE REMOVAL

LOCATION	6 TO 15 UNITS DIAMETER		OVER 15 UNITS DIAMETER UNIT
	UNIT	UNIT	
VETERANS PARKWAY			
83' RT STA 324+26	11		
85' RT STA 324+85	9		
85' RT STA 325+09	14		
81' RT STA 328+51	9		
83' RT STA 328+78	6		
OLD JACKSONVILLE RD			
64' LT STA 46+90			17
65' LT STA 46+94			16
66' LT STA 46+96			24
60' RT STA 44+24	12		
61' RT STA 44+31	14		
66' RT STA 44+78	11		
71' RT STA 45+91	10		
MONROE ST			
59' RT STA 51+04	9		
56 RT STA 51+14	7		
58 RT STA 51+15	6		
58 RT STA 51+25	7		
51 RT STA 52+13	15		
49 RT STA 52+24	12		
51 RT STA 52+52	10		
52 RT STA 52+67	13		
TOTAL	175		57

EARTHWORK

LOCATION	EARTH EXCAVATION	EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
				CU YD	CU YD
SB VETERANS PARKWAY					
MEDIAN STA 322+06.83 TO STA 332+76.07	790	595	405	190	
OUTSIDE STA 322+41.07 TO STA 332+50.00	440	330	610	-280	
OUTSIDE STA 334+25.00 TO STA 335+75.08	70	55	50	5	
NB VETERANS PARKWAY					
MEDIAN STA 333+46.17 TO STA 343+14.77	770	580	290	290	
OUTSIDE STA 333+75.00 TO STA 343+50.00	430	325	360	-35	
OUTSIDE STA 330+53.10 TO STA 332+50.00	45	35	60	-25	
LAWRENCE AVE					
RIGHT STA 14+22.00 TO STA 15+55.00	30	25	40	-15	
OLD JACKSONVILLE RD					
RIGHT STA 42+00.00 TO STA 48+50.00	350	265	300	-35	
MEDIAN STA 45+00.00 TO STA 48+50.00	40	30	0	30	
LEFT STA 40+75.00 TO STA 48+50.00	2,390	1,795	5	1,790	
MONROE ST					
MEDIAN STA 50+50.00 TO STA 11+00.00	205	155	0	155	
RIGHT STA 50+26.35 TO STA 11+00.00	2,390	1,795	675	1,120	
LEFT STA 51+00.00 TO STA 11+00.00	475	360	5	355	
RICKARD RD					
	465	350	0	350	
EAST LEG OLD JACKSONVILLE RD					
	130	100	5	95	
TOTAL	9,020	6,795	2,805	3,990	

SEEDING

LOCATION	SEEDING, CLASS 2 ACRE	FERTILIZER NUTRIENTS			AGRICULTURAL GROUND LIMESTONE TON	MULCH, METHOD 3 ACRE	TEMPORARY EROSION CONTROL SEEDING POUNDS
		NITROGEN POUNDS	PHOSPHORUS POUNDS	POTASSIUM POUNDS			
SB VETERANS PARKWAY							
OUTSIDE							
STA 322+30.00 TO STA 329+95.00	0.17	15	15	15	0.3	0.17	17
MEDIAN							
STA 322+06.00 TO STA 326+06.00	0.14	13	13	13	0.3	0.14	14
NB VETERANS PARKWAY							
OUTSIDE							
STA 333+64.00 TO STA 334+75.00	0.04	4	4	4	0.1	0.04	4
MEDIAN							
STA 339+16.00 TO STA 343+16.00	0.14	13	13	13	0.3	0.14	14
LAWRENCE AVE							
RT STA 14+25.00 TO STA 15+55.00	0.02	2	2	2	0.0	0.02	2
OLD JACKSONVILLE RD							
LT STA 40+50.00 TO STA 43+35.00	0.06	5	5	5	0.1	0.06	6
LT STA 10+15.00 TO STA 49+72.00	0.17	15	15	15	0.3	0.17	17
RT STA 42+08.00 TO STA 48+50.00	0.19	17	17	17	0.4	0.19	19
MONROE ST							
LT STA 51+02.00 TO STA 55+31.00	0.07	6	6	6	0.1	0.07	7
LT STA 55+70.00 TO STA 8+27.00	0.01	1	1	1	0.0	0.01	1
LT STA 8+67.00 TO STA 9+60.00	0.01	1	1	1	0.0	0.01	1
LT STA 9+95.00 TO STA 11+29.00	0.01	1	1	1	0.0	0.01	1
RT STA 50+00.00 TO STA 10+66.00	0.55	50	50	50	1.1	0.55	55
OLD JACKSONVILLE RD (SOUTH LEG)							
LT STA 98+06.00 TO STA 99+19.00	0.06	5	5	5	0.1	0.06	6
RT STA 98+06.00 TO STA 99+54.00	0.03	3	3	3	0.1	0.03	3
TOTAL	1.67	151	151	151	3.2	1.67	167

AGGREGATE (EROSION CONTROL)

LOCATION	TON
SB VETERANS PARKWAY	
OUTSIDE	
STA 322+00.00	8.8
MEDIAN	
STA 322+00.00	8.8
NB VETERANS PARKWAY	
MEDIAN	
STA 343+16.00	8.8
MONROE ST	
STA 53+75.00	8.8
TOTAL	35.2

PERIMETER EROSION BARRIER

LOCATION	FOOT
OLD JACKSONVILLE RD	
LT STA 40+50.00 TO STA 42+50.00	200
LT STA 48+00.00 TO STA 49+70.00	193
RT STA 42+17.00 TO STA 48+50.00	689
MONROE ST	
LT STA 51+07.00 TO STA 51+85.00	85
RT STA 51+00.00 TO STA 53+50.00	264
RT STA 54+50.00 TO STA 10+75.00	552
OLD JACKSONVILLE RD (SOUTH LEG)	
LT STA 98+06.00 TO STA 99+19.00	117
RT STA 98+06.00 TO STA 99+54.00	144
TOTAL	2,244

INLET AND PIPE PROTECTION

LOCATION	EACH
LAWRENCE AVE	
RT STA 14+25	1
TOTAL	1



JOB = 2200.4
 FILE NAME = D672B99-shd-schedule.dgn
 PLOT SCALE = 48.0000 "/ IN.
 PLOT DATE = Oct-29-2009 11:38:25AM

DESIGNED - NAK
 DRAWN - AJH
 CHECKED - NAK
 DATE - 6/26/2008

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	32
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				