

PATCHING SUMMARY

LOCATION	PAVEMENT PATCHING CLASS A				SAW CUTS FOOT	PATCHING REINFORCEMENT SQ YD	TIE BARS EACH
	TYPE 1, 8"	TYPE 2, 8"	TYPE 3, 8"	TYPE 4, 8"			
	SQ YD	SQ YD	SQ YD	SQ YD			
SB IL 4 - DRIVING LANE	64.0	373.9	16.7	156.0	4358	610.6	82
SB IL 4 - PASSING LANE	24.0	136.0	16.0	0.0	1484	176.0	0
NB IL 4 - DRIVING LANE	52.0	500.7	72.0	264.0	5825	888.7	100
NB IL 4 - PASSING LANE	16.0	136.0	0.0	0.0	1370	152.0	0
TOTAL	156.0	1,146.6	104.7	420.0	13,037	1,827.3	182

PATCHING SCHEDULE

PATCH NO.	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	PAVEMENT PATCHING CLASS A				SAW CUTS FOOT	PATCHING REINFORCEMENT SQ YD	TIE BARS EACH
					TYPE 1, 8"	TYPE 2, 8"	TYPE 3, 8"	TYPE 4, 8"			
					SQ YD	SQ YD	SQ YD	SQ YD			
SB IL 4 - DRIVING LANE											
1	271+90	6	6	4.0	4.0				42	4.0	
2	283+30	6	12	8.0		8.0			72	8.0	
3	283+50	6	12	8.0		8.0			72	8.0	
4	286+10	6	12	8.0		8.0			72	8.0	
5	286+45	6	12	8.0		8.0			72	8.0	
6	290+40	6	12	8.0		8.0			72	8.0	
7	339+00	6	12	8.0		8.0			72	8.0	
8	337+92	6	12	8.0		8.0			72	8.0	
9	336+33	6	12	8.0		8.0			72	8.0	
10	328+76	6	12	8.0		8.0			72	8.0	
11	321+00	10	6	6.7		6.7			50	6.7	
12	315+00	6	6	4.0	4.0				42	4.0	
13	313+92	8	6	5.3		5.3			46	5.3	
14	313+50	25	6	16.7			16.7		80	16.7	13
15	312+50	20	6	13.3		13.3			70	13.3	10
16	310+05	8	6	5.3		5.3			46	5.3	
17	309+50	8	6	5.3		5.3			46	5.3	
18	306+98	6	6	4.0	4.0				42	4.0	
19	304+62	8	12	10.7		10.7			76	10.7	
20	303+40	7	12	9.3		9.3			74	9.3	
21	290+75	15	6	10.0		10.0			60	10.0	
22	290+65	6	6	4.0	4.0				42	4.0	
23	290+30	8	6	5.3		5.3			46	5.3	
24	290+08	6	12	8.0		8.0			72	8.0	
25	289+13	6	6	4.0	4.0				42	4.0	
26	287+02	6	12	8.0		8.0			72	8.0	
27	286+68	6	12	8.0		8.0			72	8.0	
28	285+74	6	12	8.0		8.0			72	8.0	
29	285+17	6	6	4.0	4.0				42	4.0	
30	290+50	6	12	8.0		8.0			72	8.0	
31	290+70	6	12	8.0		8.0			72	8.0	
32	290+80	6	12	8.0		8.0			72	8.0	
33	293+00	6	12	8.0		8.0			72	8.0	
34	304+60	6	12	8.0		8.0			72	8.0	
35	305+40	6	12	8.0		8.0			72	8.0	
36	307+25	6	12	8.0		8.0			72	8.0	
37	307+40	12	6	8.0		8.0			54	8.0	
38	308+20	6	12	8.0		8.0			72	8.0	
39	308+35	6	12	8.0		8.0			72	8.0	
40	310+10	6	12	8.0		8.0			72	8.0	
41	312+60	6	12	8.0		8.0			72	8.0	
42	312+75	6	12	8.0		8.0			72	8.0	
43	313+10	6	12	8.0		8.0			72	8.0	
44	313+50	20	12	26.7			26.7		100	26.7	10
45	313+90	10	12	13.3		13.3			80	13.3	
46	314+10	6	12	8.0		8.0			72	8.0	
47	314+30	6	6	4.0	4.0				42	4.0	
48	314+50	6	6	4.0	4.0				42	4.0	
49	316+30	6	6	4.0	4.0				42	4.0	
50	316+80	6	6	4.0	4.0				42	4.0	
51	317+00	6	6	4.0	4.0				42	4.0	
52	317+90	12	6	8.0		8.0			54	8.0	
53	318+50	6	6	4.0	4.0				42	4.0	
54	320+80	6	6	4.0	4.0				42	4.0	
55	321+00	10	6	6.7		6.7			50	6.7	
56	321+30	6	6	4.0	4.0				42	4.0	
57	322+10	6	12	8.0		8.0			72	8.0	
58	322+20	6	6	4.0	4.0				42	4.0	
59	326+25	6	12	8.0		8.0			72	8.0	
60	328+80	8	12	10.7		10.7			76	10.7	
61	332+50	50	12	66.7			66.7		160	66.7	25
62	334+90	25	12	33.3			33.3		110	33.3	13
63	335+20	22	12	29.3			29.3		104	29.3	11
64	336+50	6	6	4.0	4.0				42	4.0	
65	337+75	6	12	8.0		8.0			72	8.0	
66	338+80	6	12	8.0		8.0			72	8.0	
67	339+00	6	12	8.0		8.0			72	8.0	
TOTAL					64.0	373.9	16.7	156.0	4,358.0	610.6	82

PATCHING SCHEDULE

PATCH NO.	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	PAVEMENT PATCHING CLASS A				SAW CUTS FOOT	PATCHING REINFORCEMENT SQ YD	TIE BARS EACH
					TYPE 1, 8"	TYPE 2, 8"	TYPE 3, 8"	TYPE 4, 8"			
					SQ YD	SQ YD	SQ YD	SQ YD			
SB IL 4 - PASSING LANE											
68	320+50	6	6	4.0	4.0				42	4.0	
69	286+59	6	6	4.0	4.0				42	4.0	
70	305+31	6	6	4.0	4.0				42	4.0	
71	321+60	6	6	4.0	4.0				42	4.0	
72	323+10	6	12	8.0		8.0			72	8.0	
73	325+40	6	6	4.0	4.0				42	4.0	
74	325+80	6	6	4.0	4.0				42	4.0	
75	326+10	6	12	8.0		8.0			72	8.0	
76	326+25	6	12	8.0		8.0			72	8.0	
77	326+40	6	12	8.0		8.0			72	8.0	
78	330+80	8	12	10.7		10.7			76	10.7	
79	337+50	6	12	8.0		8.0			72	8.0	
80	337+70	6	12	8.0		8.0			72	8.0	
81	337+75	6	12	8.0		8.0			72	8.0	
82	337+90	6	12	8.0		8.0			72	8.0	
83	342+60	6	12	8.0		8.0			72	8.0	
84	344+10	12	12	16.0			16.0		84	16.0	
85	344+34	6	8	5.3		5.3			52	5.3	
86	349+70	10	12	13.3		13.3			80	13.3	
87	359+34	6	12	8.0		8.0			72	8.0	
88	359+40	6	12	8.0		8.0			72	8.0	
89	363+10	8	12	10.7		10.7			76	10.7	
90	364+90	6	12	8.0		8.0			72	8.0	
TOTAL					24.0	136.0	16.0	0.0	1,484	176.0	0

PATCHING SCHEDULE

PATCH NO.	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	PAVEMENT PATCHING CLASS A				SAW CUTS FOOT	PATCHING REINFORCEMENT SQ YD	TIE BARS EACH
					TYPE 1, 8"	TYPE 2, 8"	TYPE 3, 8"	TYPE 4, 8"			
					SQ YD	SQ YD	SQ YD	SQ YD			
NB IL 4 - DRIVING LANE											
91	270+20	8	6	5.3		5.3			46	5.3	
92	280+80	6	12	8.0		8.0			72	8.0	
93	283+00	8	12	10.7		10.7			76	10.7	
94	283+00	6	12	8.0		8.0			72	8.0	
95	286+40	8	12	10.7		10.7			76	10.7	
96	286+60	6	12	8.0		8.0			72	8.0	
97	286+61	6	12	8.0		8.0			72	8.0	
98	286+70	6	12	8.0		8.0			72	8.0	
99	286+90	6	12	8.0		8.0			72	8.0	
100	287+00	6	6	4.0	4.0				42	4.0	
101	287+50	8	12	10.7		10.7			76	10.7	
102	288+00	20	12	26.7			26.7		100	26.7	10
103	288+00	6	12	8.0		8.0			72	8.0	
104	289+10	6	12	8.0		8.0			72	8.0	
105	290+20	8	12	10.7		10.7			76	10.7	
106	297+40	6	12	8.0		8.0			72	8.0	
107	297+50	6	12	8.0		8.0			72	8.0	
108	298+00	6	12	8.0		8.0			72	8.0	
109	299+60	6	12	8.0		8.0			72	8.0	
110	299+75	6	12	8.0		8.0			72	8.0	
111	300+44	6	12	8.0		8.0			72	8.0	
112	300+80	6	12	8.0		8.0			72	8.0	
113	301+00	6	12	8.0		8.0			72	8.0	
114	301+30	10	12	13.3		13.3			80	13.3	
115	301+50	6	12	8.0		8.0			72	8.0	
116	302+00	6	12	8.0		8.0			72	8.0	
117	302+65	6	12	8.0		8.0			72	8.0	
118	303+00	26	12	34.7			34.7		112	34.7	13
119	303+00	12	12	16.0			16.0		84	16.0	
120	303+52	6	12	8.0		8.0			72	8.0	
121	304+40	18	12	24.0		24.0			96	24.0	
122	304+60	8	12	10.7		10.7			76	10.7	
123	304+70	12	12								