

STORM SEWER REMOVAL 12'

LOCATION	FOOT
<b>VETERANS PARKWAY</b>	
14.9' LT STA 330+88.6 TO 10.3' LT STA 330+88.6	4.6
10.3' LT STA 330+88.6 TO 6.2' LT STA 330+88.6	4.1
6.2' LT STA 330+88.6 TO 11.8' RT STA 331+19.4	36.4
11.8' LT STA 331+19.4 TO 6.8' LT STA 332+69.5	150.1
14.8' LT STA 333+54.8 TO 14.8' LT STA 335+05.5	150.7
14.8' LT STA 335+05.5 5.2' RT STA 335+30.4	32.0
5.2' RT STA 335+30.4 TO 9.6' RT STA 335+30.4	4.4
9.6' RT STA 335+30.4 TO 14.7' RT STA 335+30.4	5.1
<b>OLD JACKSONVILLE RD</b>	
31.55' LT STA 40+65.8 TO 31.5' LT STA 40+77.7	11.9
31.6' LT STA 43+10.8 TO 41.6' LT STA 43+10	10.4
41.6' LT STA 43+10 TO 44.4' LT STA 43+38	21.1
39.9' LT STA 43+93.6 TO 32.9' LT STA 44+77.7	80.4
32.9' LT STA 44+77.7 TO 33.0' LT STA 44+90.9	12.6
39.6' RT STA 44+49.5 TO 35.9' RT STA 44+53.1	5.3
33.0' LT STA 44+90.9 TO 2.4' LT STA 44+91.3	30.6
2.4' LT STA 44+91.3 TO 0.4' LT STA 45+24.8	33.5
34.3' LT STA 46+51.1 TO 3.75' RT STA 46+51.5	38.0
<b>MONROE ST</b>	
42.8' LT STA 54+26.4 TO 39.6' LT STA 54+62.7	34.7
17.25' RT STA 54+69.1 TO 44.8' RT STA 54+77.3	28.9
6.9' RT STA 7+09.3 TO 0.9' RT STA 7+55.4	46.5
40.9' RT STA 9+33.4 TO 34.5' RT STA 9+50.1	17.9
<b>TOTAL</b>	<b>759.2</b>

PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)

LOCATION	SQ YD
<b>VETERANS PARKWAY</b>	
STA 279+58.80 TO STA 280+25.60	27.03
STA 283+02.00 TO STA 283+32.00	10.00
STA 283+72.20 TO STA 284+36.65	29.19
STA 301+67.35 TO STA 302+07.35	13.04
STA 302+70.00 TO STA 303+27.00	19.00
STA 304+87.00 TO STA 304+25.00	18.00
STA 306+09.35 TO STA 306+47.35	12.54
<b>OLD JACKSONVILLE RD</b>	
STA 44+18.75 TO STA 45+02.50	44.36
<b>MONROE ST</b>	
STA 13+74.90 TO STA 15+25.05	72.44
<b>TOTAL</b>	<b>245.60</b>

HOT-MIX ASPHALT SURFACE REMOVAL, 2"

LOCATION	WIDTH FOOT	SQ YD
<b>OLD JACKSONVILLE ROAD</b>		
STA 22+10.00 TO STA 40+55.54	60	12,303.60
<b>KOKE MILL ROAD</b>		
STA 109+39.00 TO STA 110+09.52	72' & VARY	721.00
STA 110+71.79 TO STA 111+51.50	44' & VARY	510.89
<b>WESTON POINTE DRIVE</b>		
STA 99+44.00 TO STA 99+70.00	26' & VARY	119.44
<b>WAKEFIELD DRIVE</b>		
STA 100+30.00 TO STA 100+56.00	26' & VARY	126.11
<b>WOODMILL DRIVE</b>		
STA 99+44.00 TO STA 99+70.00	26' & VARY	183.33
<b>TOTAL</b>		<b>13964.37</b>

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

LOCATION	WIDTH FOOT	SQ YD
<b>SB VETERANS PARKWAY</b>		
STA 283+02.08 TO STA 298+00.00	10	1,664.36
STA 304+87.82 TO STA 315+55.00	10	1,185.76
<b>NB VETERANS PARKWAY</b>		
STA 274+30.00 TO STA 281+07.65	10	752.94
STA 287+45.00 TO STA 303+26.66	10	1,757.40
STA 343+45.00 TO STA 365+20.00	10	2,416.67
<b>OLD JACKSONVILLE ROAD</b>		
STA 40+53.54 TO STA 40+93.54	40	177.78
<b>TOTAL</b>		<b>7,954.91</b>

CONCRETE CURB, TYPE B

LOCATION	FOOT
<b>WASHINGTON ST</b>	
<b>CORNER ISLANDS</b>	
LT STA 35+04.90 TO STA 35+29.55	31
LT STA 36+36.35 TO STA 36+50.05	30
RT STA 34+96.75 TO STA 35+27.50	37
RT STA 36+34.50 TO STA 36+56.40	28
<b>LAWRENCE AVE</b>	
<b>CORNER ISLANDS</b>	
LT STA 12+61.55 TO STA 12+83.00	16
LT STA 13+89.60 TO STA 14+07.20	21
RT STA 13+86.90 TO STA 14+12.35	12
<b>OLD JACKSONVILLE RD/MONROE ST</b>	
<b>CORNER ISLANDS</b>	
LT STA 49+03.08 TO STA 49+37.90	46
LT STA 49+89.09 TO STA 50+78.99	37
RT STA 48+66.95 TO STA 48+99.51	42
RT STA 50+11.52 TO STA 50+46.30	46
<b>MEDIANS</b>	
LT STA 49+76.47 TO STA 49+89.09	23
RT STA 49+59.24 TO STA 49+72.40	23
<b>RICKARD ROAD ENTRANCES</b>	
RT STA 11+48.00	69.0
<b>MONROE ST ENTRANCES</b>	
LT STA 55+53.80	41.2
LT STA 8+47.18	45.5
LT STA 9+78.00	49.5
<b>CLOCKTOWER DR ENTRANCES</b>	
LT STA 50+90.35	41
<b>TOTAL</b>	<b>638</b>
<b>CONCRETE CURB, TYPE B (SPECIAL)</b>	
LOCATION	FOOT
<b>WASHINGTON ST</b>	
<b>MEDIANS</b>	
LT STA 35+68.05 TO STA 35+80.25	18
RT STA 35+83.50 TO STA 35+96.30	18
<b>LAWRENCE AVE</b>	
<b>MEDIANS</b>	
LT STA 13+20.20 TO STA 13+34.40	20
<b>TOTAL</b>	<b>56</b>
<b>COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18</b>	
LOCATION	FOOT
<b>WASHINGTON ST</b>	
<b>SIDEWALK RAMPS</b>	
LT STA 34+88.40 TO STA 35+00.50	16.4
LT STA 36+59.50 TO STA 36+80.90	26.0
RT STA 34+87.90 TO STA 35+01.90	16.5
RT STA 36+58.10 TO STA 36+75.30	22.1
<b>OLD JACKSONVILLE RD</b>	
LT STA 40+53.54 TO STA 43+08.14	254.6
RT STA 40+53.54 TO STA 41+48.21	94.7
<b>WOODS FARM RD</b>	
LT STA 0+30.50 TO STA +70.80	57.5
<b>RICKARD RD</b>	
LT STA 10+39.06 TO STA 12+00.00	179.9
<b>TOTAL</b>	<b>667.7</b>
<b>COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (VARIABLE WIDTH GUTTER FLAG)</b>	
LOCATION	FOOT
<b>WASHINGTON ST</b>	
<b>CORNER ISLANDS</b>	
LT STA 35+04.90 TO STA 35+29.55	37
LT STA 36+36.35 TO STA 36+50.05	37
RT STA 34+96.75 TO STA 35+27.50	50
RT STA 36+34.50 TO STA 36+56.40	37
<b>OLD JACKSONVILLE RD/MONROE ST</b>	
LT STA 50+49.70 TO STA 50+78.99	29
RT STA 48+66.95 TO STA 48+99.51	33
<b>TOTAL</b>	<b>223</b>

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

LOCATION	FOOT
<b>OLD JACKSONVILLE RD</b>	
LT 44+36.27 TO STA 49+76.67	560.1
RT 42+43.81 TO STA 48+41.88	725.2
<b>MONROE ST</b>	
LT 51+04.17 TO STA 55+72.35	557.9
LT 6+56.47 TO STA 11+30.06	471.7
RT 49+83.00 TO STA 55+72.35	656.6
RT 6+56.47 TO STA 10+58.09	401.8
<b>WOODS FARM RD</b>	
RT STA 0+30.50 TO STA +70.80	58.6
<b>RICKARD RD</b>	
RT STA 10+54.23 TO STA 12+00.00	174.9
<b>OLD JACKSONVILLE RD (SOUTH LEG)</b>	
LT 98+06.13 TO STA 99+44.75	175.2
RT 98+82.30 TO STA 99+71.24	157.3
<b>TOTAL</b>	<b>3,939.3</b>
<b>COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06</b>	
LOCATION	FOOT
<b>WASHINGTON ST</b>	
<b>CORNER ISLANDS</b>	
LT STA 35+04.90 TO STA 35+29.55	28
LT STA 36+36.35 TO STA 36+50.05	27
RT STA 34+96.75 TO STA 35+27.50	34
RT STA 36+34.50 TO STA 36+56.40	26
<b>MEDIANS</b>	
LT STA 35+68.05 TO STA 35+80.25	25
RT STA 35+83.50 TO STA 35+96.30	12
<b>VETERANS PARKWAY</b>	
<b>INLETS TO BE ADJUSTED</b>	
LT STA 281+03.25 TO STA 281+15.25	12
RT STA 281+63.00	10
LT STA 283+58.75 TO STA 283+70.75	12
RT STA 283+88.25 TO STA 284+00.25	12
LT STA 302+06.35 TO STA 302+18.35	12
RT STA 302+31.25 TO STA 302+43.25	12
LT STA 304+45.00 TO STA 304+57.00	12
RT STA 304+93.90 TO STA 305+05.90	12
<b>LAWRENCE AVE</b>	
<b>CORNER ISLANDS</b>	
LT STA 12+61.55 TO STA 12+83.00	24
LT STA 13+89.60 TO STA 14+07.20	22
RT STA 12+60.60 TO STA 12+81.60	25
RT STA 13+86.90 TO STA 14+12.35	29
<b>MEDIANS</b>	
LT STA 13+20.20 TO STA 13+34.40	20
<b>OLD JACKSONVILLE RD/MONROE ST</b>	
LT STA 49+03.08 TO STA 49+37.90	50
LT STA 50+65.00 TO STA 50+78.99	25
RT STA 48+66.95 TO STA 48+99.51	50
RT STA 50+11.52 TO STA 50+46.30	28
<b>TOTAL</b>	<b>519</b>
<b>CONCRETE GUTTER, TYPE B (SPECIAL)</b>	
LOCATION	FOOT
<b>LAWRENCE AVE</b>	
LT STA 11+18.00 TO STA 12+47.55	134.9
LT STA 12+56.48 TO STA 12+75.18	38.2
LT STA 13+94.15 TO STA 14+06.60	30.3
LT STA 14+22.65 TO STA 15+55.00	138.3
RT STA 11+18.00 TO STA 12+77.30	180.2
RT STA 13+92.60 TO STA 14+17.75	54.2
RT STA 14+27.25 TO STA 15+55.00	132.3
<b>CLOCKTOWER DR</b>	
LT STA 50+57.20 TO STA 51+49.25	92.1
RT STA 50+36.04 TO STA 51+49.25	123.4
<b>DURKIN DR</b>	
LT STA 10+29.60 TO STA 11+12.00	94.8
RT STA 10+28.60 TO STA 10+59.00	47.1
RT STA 10+71.00 TO STA 11+12.00	40.0
<b>TOTAL</b>	<b>1,103.8</b>

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24

LOCATION	FOOT
<b>WASHINGTON ST</b>	
<b>MEDIANS</b>	
LT STA 35+68.05 TO STA 35+80.25	12.0
RT STA 35+83.50 TO STA 35+96.30	19.0
<b>VETERANS PARKWAY</b>	
<b>INLETS TO BE ADJUSTED</b>	
LT STA 280+99.00 TO STA 281+11.00	12.0
RT STA 283+88.05 TO STA 284+00.05	12.0
LT STA 302+06.35 TO STA 302+18.35	12.0
RT STA 304+85.90 TO STA 304+97.90	12.0
<b>LAWRENCE AVE</b>	
<b>CORNER ISLANDS</b>	
LT STA 12+61.55 TO STA 12+83.00	29.4
LT STA 13+89.60 TO STA 14+07.20	29.1
RT STA 12+60.60 TO STA 12+81.60	31.4
RT STA 13+86.90 TO STA 14+12.35	31.5
<b>MEDIANS</b>	
LT STA 13+20.20 TO STA 13+34.40	7.1
<b>OLD JACKSONVILLE RD/MONROE ST</b>	
LT STA 49+03.08 TO STA 49+37.90	65.0
LT STA 50+49.70 TO STA 50+78.99	29.0
RT STA 48+66.95 TO STA 48+99.51	31.0
RT STA 50+11.52 TO STA 50+46.30	65.0
STA 12+02.90 TO STA 12+09.40	15.0
<b>TOTAL</b>	<b>412.5</b>

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24

LOCATION	FOOT
<b>VETERANS PARKWAY</b>	
LT STA 326+06.55 TO STA 331+84.68	582.63
RT STA 327+34.82 TO STA 332+74.01	553.19
LT STA 333+48.34 TO STA 337+89.77	455.43
RT STA 334+39.57 TO STA 339+16.11	481.04
<b>TOTAL</b>	<b>2,072.29</b>

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06

LOCATION	FOOT
<b>VETERANS PARKWAY</b>	
LT STA 326+06.55 TO STA 331+84.68	578.13
RT STA 327+34.82 TO STA 332+74.01	539.19
RT STA 333+48.34 TO STA 337+89.77	441.43
LT STA 334+39.57 TO STA 339+16.11	476.54
<b>TOTAL</b>	<b>2,035.29</b>

CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)

LOCATION	SQ FT
<b>OLD JACKSONVILLE RD</b>	
STA 43+84.55 TO STA 48+26.11	2,418.00
<b>MONROE ST</b>	
STA 51+20.62 TO STA 55+72.35	1,825.70
STA 6+56.47 TO STA 10+78.09	1,516.25
<b>TOTAL</b>	<b>5,759.95</b>

CONCRETE GUTTER, TYPE A

LOCATION	FOOT
<b>VETERANS PARKWAY</b>	
RT STA 300+46.00 TO STA 303+20.00	274
<b>TOTAL</b>	<b>274</b>

CLASS SI CONCRETE (OUTLET)

LOCATION	CU YD
<b>LAWRENCE AVE</b>	
LT STA 12+50.45	0.7
LT STA 14+15.80	0.7
<b>CLOCKTOWER DR</b>	
RT STA 50+55.00	4.2
<b>DURKIN DR</b>	
RT STA 10+65.00	0.7
<b>TOTAL</b>	<b>6.3</b>



JOB = 2200.4  
 FILE NAME = D672B99-sh-t-schedule.dgn  
 PLOT SCALE = 48,0000 "/>

DESIGNED - NAK  
 DRAWN - AJH  
 CHECKED - NAK  
 DATE - 6/26/2008

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	36
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				