

LOCATION	OFFSET	MANHOLES TO BE ADJUSTED	INLETS TO BE ADJUSTED	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	REMOVING MANHOLES	REMOVING INLETS
		EACH	EACH	EACH	EACH	EACH	EACH	EACH
VETERANS PARKWAY								
LT STA 281+09.60	15.85			1				
LT STA 281+05.00	9.00			1				
RT STA 281+61.00	10.10			1				
LT STA 283+64.75	15.30			1				
RT STA 283+94.10	5.25			1				
RT STA 283+94.25	14.50			1				
LT STA 302+11.25	13.60			1				
LT STA 302+11.25	4.30			1				
RT STA 302+37.25	15.25			1				
LT STA 304+50.85	16.50			1				
RT STA 304+92.00	9.95			1				
RT STA 305+00.15	14.60			1				
LT STA 330+88.65	14.90							1
LT STA 330+88.65	10.30							1
LT STA 330+88.65	6.15							1
RT STA 331+19.40	13.85							1
RT STA 332+69.50	6.75							1
LT STA 333+54.80	14.85							1
LT STA 335+05.50	14.80							1
RT STA 335+30.00	5.20							1
RT STA 335+30.00	9.60							1
RT STA 335+30.00	14.70							1
WASHINGTON STREET								
LT STA 36+75.90	47.65			1				
RT STA 36+69.35	53.00			1				
LAWRENCE AVE								
RT STA 14+34.30	43.85		1					
OLD JACKSONVILLE RD								
RT STA 40+66.00	32.40		1					
RT STA 40+77.75	32.40		1					
LT STA 40+65.80	31.55							1
LT STA 40+77.70	31.55							1
RT STA 41+58.70	34.23		1					
LT STA 43+09.95	42.00						1	
LT STA 43+10.80	31.65							1
LT STA 43+37.95	44.45							1
LT STA 43+93.60	39.90							1
RT STA 44+53.00	35.90	1						
LT STA 44+77.75	32.90							1
LT STA 44+90.85	33.00							1
RT STA 44+49.55	39.55							1
LT STA 44+91.25	2.39						1	
LT STA 45+24.80	0.40							1
LT STA 45+63.60	0.85							1
RT STA 46+51.55	3.75				1			
LT STA 46+51.10	34.30							1
RT STA 47+18.25	46.10							1
MONROE ST								
RT STA 51+83.90	34.30							1
LT STA 51+84.45	45.40							1
RT STA 52+23.10	6.75							1
LT STA 52+92.10	35.85	1						
LT STA 54+60.80	4.80					1		
RT STA 54+77.30	44.80	1						
LT STA 54+26.40	42.85							1
LT STA 54+62.65	39.60							1
RT STA 7+09.30	6.85							1
RT STA 7+55.20	34.35					1		
RT STA 7+55.40	0.90						1	
RT STA 7+63.90	43.05	1						
RT STA 9+33.40	4.90	1						
LT STA 9+40.55	34.60		1					
RT STA 9+50.10	34.50							1
RT STA 11+77.70	46.50							
TOTAL		5	6	14	1	2	4	28

CONCRETE COLLAR	
LOCATION	EACH
LAWRENCE AVE	
RT STA 14+55.00	1
MONROE ST	
LT STA 51+84.70	1
RT STA 51+83.90	1
LT STA 54+63.20	1
TOTAL	4

PIPE UNDERDRAINS 4"		FOOT
LOCATION		
VETERANS PARKWAY		
LT STA 322+07.75	TO STA 326+00.00	392
LT STA 326+25.00	TO STA 327+35.00	110
LT STA 327+50.00	TO STA 329+22.00	172
RT STA 327+50.00	TO STA 329+22.00	172
LT STA 329+25.00	TO STA 330+85.00	160
RT STA 329+25.00	TO STA 330+85.00	160
LT STA 330+89.00	TO STA 331+74.00	85
RT STA 330+89.00	TO STA 331+74.00	85
RT STA 331+75.00	TO STA 332+58.00	83
LT STA 333+58.00	TO STA 334+00.00	42
LT STA 334+04.00	TO STA 334+50.00	46
RT STA 334+52.00	TO STA 335+30.00	78
LT STA 334+52.00	TO STA 335+30.00	78
RT STA 335+32.00	TO STA 337+75.00	243
LT STA 335+32.00	TO STA 337+75.00	243
RT STA 337+77.00	TO STA 339+00.00	123
RT STA 339+02.00	TO STA 343+15.00	413
TOTAL		2,685

PIPE UNDERDRAINS 4" (SPECIAL)		FOOT
LOCATION		
STA 332+07.75		19
STA 343+15.00		19
TOTAL		38

CONCRETE HEADWALL FOR PIPE DRAINS		EACH
LOCATION		
STA 332+07.75		1
STA 343+15.00		1
TOTAL		2

PIPE UNDERDRAIN REMOVAL		FOOT
LOCATION		
NB VETERANS PARKWAY		
STA 326+08.80	TO STA 332+25.00	MEDIAN SHOULDER 616
STA 322+41.00	TO STA 330+35.00	OUTSIDE SHOULDER 794
STA 334+00.00	TO STA 343+14.00	MEDIAN SHOULDER 914
SB VETERANS PARKWAY		
STA 331+18.00	TO STA 332+68.00	MEDIAN SHOULDER 150
STA 333+53.00	TO STA 335+20.00	MEDIAN SHOULDER 167
TOTAL		2,641



JOB = 2200.4
FILE NAME = D672B99-shd-schedule.dgn
PLOT SCALE = 48.0000 "/ IN.
PLOT DATE = Oct-29-2009 11:32:03AM

DESIGNED - NAK
DRAWN - AJH
CHECKED - NAK
DATE - 6/26/2008

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(2-1-2, 2-2) RS, TS-6	SANGAMON	244	41
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				