



STORM SEWERS						STRUCTURES														
NO.	LOCATION	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12\"	STORM SEWERS, TYPE 1, RCCP, CL 4, 12\"	USFL ELEVATION	DSFL ELEVATION	CLSM	NO.	LOCATION	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	FLOWLINE GRATE	FLOWLINE 12\" EAST	FLOWLINE 12\" WEST	FLOWLINE 12\" NORTH	FLOWLINE 12\" SOUTH				
		EACH	FOOT			CU YD														
IL4 - EB TURN LANE																				
S1	75.5' LT - 69.5' LT	1		602.1	602.0		M1	18.75' LT STA 326+25			1	605.70	602.5	602.6		602.7				
S2	20.25' LT - 69.5' LT		49.25	602.5	602.1	13.5	A2	6.00' LT STA 326+25	1			605.33	602.7							
S3	6.5' LT - 17.25' LT		10.75	602.7	602.6	3.3	A3	18.75' LT STA 327+50	1			606.13		603.2						
S4	18.75' LT STA 326+26.5 TO 13' LT STA 327+48.5		123	603.0	602.7	25.7	M4	13.00' LT STA 327+50			1	605.95	603.1	603.1	603.1	603.1				
S5	18.25' LT - 14.5' LT		3.75	603.2	603.1	0.9	B5	13.00' RT STA 327+50		1		605.95	603.3	603.3						
S6	11.5' LT - 12' RT		23.5	603.3	603.1	6.7	A6	18.75' RT STA 327+50	1			606.13	603.4							
S7	14' RT - 18.25' RT		4.25	603.4	603.3	0.9	A7	18.75' LT STA 329+25			1	606.64		603.6						
S8	13' LT STA 327+51 TO 13' LT STA 329+24		173	603.5	603.1	58.6	M8	13.00' LT STA 329+25			1	606.46	603.5	603.5	603.5					
S9	18.25' LT - 14.5' LT		3.75	603.6	603.5	1	B9	13.00' RT STA 329+25		1		606.46	603.7	603.7						
S10	11.5' LT - 12' RT		23.5	603.7	603.5	5.4	A10	18.75' RT STA 329+25	1			606.64		603.8						
S11	14' RT - 18.25' RT		4.25	603.8	603.7	1.9	B11	18.75' LT STA 330+88.60			1	607.11	603.6	603.6						
S12	17' LT - 14.5' LT		3.5	603.6	603.5	0.5	M12	13.00' LT STA 330+88.60			1	606.93	603.8	603.8		603.8				
S13	11.5' LT - 12' RT		23.5	604.0	603.8	1.4	B13	13.00' RT STA 330+88.60		1		606.93	604.0	604.0						
S14	14' RT - 18.25' RT		4.25	604.1	604.0	0.2	A14	18.75' RT STA 330+88.60	1			607.11	604.1							
SHEET TOTAL		1	450.25			120.0	SHEET TOTAL										6	4	4	



JOB = 2200.4
 FILE NAME = *FILES*
 PLOT SCALE = *SCALE*
 PLOT DATE = *DATE*

DESIGNED - NAK
 DRAWN - AJH
 CHECKED - NAK
 DATE - 10/08/2009

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

IL 4 (VETERANS PARKWAY) - DRAINAGE
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE. 662	SECTION (2-1-2, 2-2) RS, TS-6	COUNTY SANGAMON	TOTAL SHEETS 244	SHEET NO. 101
CONTRACT NO. 72B99				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				